

CONCRETE AND CONSTRUCTIONAL ENGINEERING

INCLUDING PRESTRESSED CONCRETE

APRIL 1960



VOL. LV. NO. 4

FIFTY-FIFTH YEAR OF PUBLICATION

PRICE 2s.

ANNUAL SUBSCRIPTION 24s. POST FREE. \$3.70 in Canada and U.S.A.

LEADING CONTENTS

	PAGE
Concrete in the Gas Industry	145
The Analysis of Symmetrical Single-bay Multiple-story Frames	
By K. Brzezinski	147
Exposed-aggregate Slabs in the South of England	155
Precast Construction of a Factory	161
Concrete at Bradwell Nuclear Power Station	164
A New Bridge over the Mersey near Manchester	165
Nomograms for the Design of Beams and Slabs by the Load-factor Method.—III.	
By J. C. Steedman	169
New Dams for Hydro-electric Works in Scotland	175
A Tunnel Lining with Dry Joints	179
Deterioration of Concrete due to Alkali Reaction	181

No. 429

ISSUED MONTHLY

Registered for
Canadian Magazine Post

BOOKS ON CONCRETE

For Catalogue of "Concrete Series" books on concrete and allied subjects, send a postcard to:

CONCRETE PUBLICATIONS LTD., 14 DARTMOUTH ST., LONDON, S.W.1.

INDEX OF ADVERTISERS

[illegible]

1½ MILLION CUBIC YARDS OF CONCRETE HAVE BEEN AIR-ENTRAINED WITH FEBCRETE A.E.A.

**ON BRITISH GOVERNMENT CONTRACTS
DURING THE PAST TWO YEARS**

FEBCRETE Air-Entraining Agent without adding to cost improves the flowability and workability of concrete, allows the water-cement ratio to be reduced and increases resistance to the passage of water and to repeated cycles of freezing and thawing.

It ensures that full compaction and maximum compressive strength are obtained without excessive vibration, reduces segregation of the aggregates and prevents bleeding. Write for brochure.

FEB (GREAT BRITAIN) LTD


LONDON: 102 Kensington High Street, W.8.

Telephone: WE5tern 0444

MANCHESTER: Albany Works, Albany Road, Chorlton-cum-Hardy.

Telephone: CHOrlton 1063

BAR-BENDING EQUIPMENT




RAS.40 MODEL

This is a single-disc machine which is specially designed for an extraordinarily high rate of bending bars up to $1\frac{1}{2}$ in. diameter.

A full hook takes three seconds' bending time. It is also equipped with accessories for bending angle loops in one operation on mild steel reinforcement up to 1 in. diameter.

HOOPS & SPIRALS

We supply, at extra cost, an appliance (illustrated here) for use with RAS.40 and ARD.50 models for the bending of hoops and spirals. Bends radii of 11 in. and upwards and to any pitch of spiral.



Our Bending Equipment also includes the ARD.50 model—a double-disc machine for bending bars up to 2 in. diameter. We also supply, at extra cost, formers and backrests for special steel such as "Square Grip," "Twiststeel," etc., which can be fitted to the ARD.50 and RAS.40 models. Full details are available on request. All machines are available for Sale or Hire.

CEMENT & STEEL, LTD., SECOND AVENUE, CHATHAM, KENT

Telephone: Chatham 45580.

Telegrams & Cables: Cembelgi, Chatham

SHOREHAM HARBOUR DEVELOPMENT



The improvement of the harbour facilities at Shoreham to accommodate larger colliers feeding Brighton 'B' power station comprised the construction of three new breakwaters, a new lock, lay-by wharves and ancillary works including extensive dredging

consulting engineers

Sir William Halcrow and Partners

CONTRACTORS

PETER LIND & COMPANY LIMITED

LONDON

ROMNEY HOUSE, TUFTON STREET, LONDON, S.W.1

TELEPHONE ABBEY 7361

CONTRACTORS! Do you know that

GLASS FIBRE FORMWORK

by comparison in speed of erection,
lightness of handling and quality of
finish, completely outclasses all other
methods?

DESIGNERS! Do you know that with

GLASS FIBRE you now have more
freedom of design, with unlimited size,
double curvatures and intricate shapes?

POLYGLAS

Consult

D. A. MODELS • LTD

108 WOODSTOCK ROAD, LONDON, W.4.

TELEPHONE: CHISWICK 2011

AND

IF

PILING

SHOULD BE NECESSARY




HOLST
NEWCASTLE

Head Office:

46 CLARENDON ROAD
WATFORD

Telephone: Watford 34481

Branches: BIRMINGHAM • MANCHESTER • LEEDS • DURHAM • EDINBURGH • CARDIFF



OUTSTANDING BUILDING . . .

Outstanding products

**CHEMICAL
BUILDING
PRODUCTS
LIMITED**
Warple Works
Cleveland Road
Hemel Hempstead
Herts.

CHEMICAL BUILDING PRODUCTS LTD

Telephone: Boxmoor
4900 (3 lines)

Telegrams: Prolithu
Hemel Hempstead

We shall be pleased
to supply full des-
criptive literature.

- PROLAPIN** Liquid Cement Waterproofer
LITHURIN Concrete Floor Hardener
QUICKSocreTE P.Q. & D. Rapid Hardeners and
Setters
WETEXI 'S' Colourless Silicone Waterproofer
CONPLAST Concrete Plasticiser
CONPLAST 'W' Anti-freeze and Plasticiser
CEBEX 112 Mortar Improver
CEBEX 113 Expanding Grouting Material
CEBEX 124 Multi-purpose Slurry Liquid
ROAD CONPLAST Air Entrainer and Plasticiser
CONBEX Plasticised Expanding Grouting Material

LIFTOYL Floor Cleaner and Degreaser

ORKIT & TEKAM Bituminous Coatings and
Compounds

CONCURE Concrete Curing Agent

NITOLUX & ROBRITE Paints

LEDNOCK DAM




FOR THE NORTH OF SCOTLAND
HYDRO-ELECTRIC BOARD

Consulting Engineers: **Sir M. MacDonald & Partners**

Difficult access to remote sites is no barrier to the establishment of Taylor Woodrow methods in the field. Here at Lednock is yet another example of the Taylor Woodrow 'full-mechanization' policy in action. Excavating thousands of tons of rock; winning and processing of aggregates; placing 110,000 cubic yards of concrete and hundreds of other operations — to each of these were directed our extensive resources in modern plant and equipment. Full mechanization means greater speed and economy combined with sound construction.

TAYLOR WOODROW

BUILD EVERYWHERE




10 PARK STREET • LONDON W.1 • GROSVENOR 8871

PSC FOR A

FREYSSINET PRESTRESSING a


THE FREYSSINET SYSTEM

The Freyssinet cone anchorage is a simple wedge, the female part being a conical steel-wound lining heavily reinforced with high-tensile steel spirals to resist bursting forces. The male part is a strong steel tube around which mesh reinforced concrete is built up to form a similar conical shape. Available sizes 8/200", 10/200", 12/200" and 12/276".




THE FREYSSI-STRAND SYSTEM

The Freysli-Strand anchorage is based on the use of the standard Freyssinet female cone in which the strand is anchored centrally with a three-jaw steel serrated wedge. Tensioning is carried out with a hollow-ram type jack hydraulically operated with automatic ramming and de-wedging devices. The system is designed for use with the following diameters of strand: 0.6", 0.7", 1" and 1 1/4".



THE FREYSSINET MULTI-STRAND SYSTEM

The Freyssinet Multi-Strand system is similar in principle to the traditional Freyssinet 12-wire system, in that the twelve half-inch strands are tensioned and anchored simultaneously. The female anchorage is made of high-quality steel, and the male cone, also of steel, is serrated along the fluted surfaces. The 12/1/2" Multi-Strand cable provides a prestressing force equivalent to 2.5 times that of a 12/276" wire cable.



PIONEERS OF PRESTRESSED CONCRETE IN GREAT BRITAIN

Other prestressing equipment supplied by us includes Hydraduct Sheath, Grouting Equipment, Pre-tensioning Jacks, etc. We also supply the Freyssinet Bridge Bearing Pads, and Freyssinet Flat Jacks.

Full details and complete technical information on prestressing equipment are always available on request.


FOR ALL PRESTRESSING EQUIPMENT

NG and P.S.C. PRESTRESSING




P.S.C. MONOWIRE SYSTEM

The P.S.C. MonoWire anchorage is based on the use of a single piece "collet" sleeve wedging in a conical hole; all sleeves are serrated internally to give absolutely positive gripping. In all cases the principal component of the various anchorage assemblies is a steel truncated guide which leads each wire from its compact cable position to its point of anchorage through a gentle curvature. MonoWire anchorages are available for 1, 2, 4, 8 and 12 wire cables of wire sizes up to and including 0.176".



P.S.C. MONOWIRE TANK ANCHORAGE

The P.S.C. MonoWire tank anchorage has been developed to provide a compact jacking and anchorage point for circumferential prestressing wires used in tank construction. It consists of a strong cast Meehanite guide working in conjunction with individual P.S.C. MonoWire sleeves and bushes. The guide is designed so that four opposing wires may be anchored at 1" centres, and at the same time allowing a further four wires to pass through grooves under the guide to provide an effective wire spacing of $\frac{1}{2}$ " centres.



P.S.C. MONOSTRAND SYSTEM

The P.S.C. MonoStrand system is similar in principle to the MonoWire system in that the anchorage jaws wedge in a conical hole. Two types of MonoStrand anchorage have been developed for use internally or externally. The type illustrated comprises a steel truncated guide cast into the end of a concrete member and the strand anchored by means of serrated steel jaws. External bushes are available for use with bearing plates. Anchorages have been developed for use with all sizes of strand up to and including $\frac{1}{2}$ " diameter.

PSC



EQUIPMENT LTD

HEAD OFFICE AND WORKS: ARUNDEL ROAD, INDUSTRIAL TRADING ESTATE, UXBRIDGE, MIDDXX

Telephone: Uxbridge 5241

INSEPARABLE from REINFORCEMENT



... OF COURSE!

**and a guarantee that
the specified concrete cover
is accurately maintained . . .**

Complying in ALL respects to the British Standard & Codes of Practice. The U-KLIPON BAR SPACER of revolutionary design is instantly fixed with a vice-like grip in the desired position on all types of reinforcement, including mesh and prefabricated. As an inseparable part it positively cannot be displaced by heavy tamping or vibrating. For any Bar Spacing problem,

CONSULT THE B.E.C. BAR SPACER SERVICE

which has been and is responsible for the most outstanding and prominent contribution to accurate bar spacing in reinforced concrete, thus providing precision, economy, and labour-saving means of ensuring that the specified concrete "cover" is maintained under all conditions. It is noteworthy that such is the increasing popularity and demand for "B.E.C." Bar Spacers, borne out by sales in excess of 35 millions, that we are able to RETAIN OUR PRICE LIST OF 1945 WITHOUT MODIFICATION. Over 120 stock sizes of bar spacers enable us to give immediate attention to requirements. Write now for comprehensive details and samples. Our Technical Consultants will call on request.

Patent Nos. 597,505, 715,563, 789,018, 810,530.

Registered Nos. 870,560, 886,239. English and foreign patents pending.



B.E.C. BEARER BLOCK FOR GROUND BEAMS · BARREL ROOFING BRIDGES · MAT WORK · ETC.

The "B.E.C." precision-made bearer block is another inexpensive B.E.C. aid to obtain accuracy with speed in concrete construction. Let us send you full details.

Enhance your Prestige.
Specify and use with
confidence.

BERRY'S ENGINEERING CO.

SOLE MANUFACTURERS:

Middle Road, Shoreham-by-Sea, Sussex


Phone and Grams: Shoreham-by-Sea 3841-2

CONTRACTORS TO MINISTRY OF SUPPLY, ETC., ETC.

boltless dry-joint TUNNEL segments

SPEEDY FIXING EASY HANDLING

Many thousands of these precast concrete segments have been used for a water main, 19 miles long with a diameter of 8 ft. 10½ in., from Hampton to Chingford. These segments eliminate the use of bolts and grouting, speed up construction, and make considerable savings in labour costs. They can be supplied for any diameter tunnel. Full technical details are available on request.



DEVELOPED AND MANUFACTURED BY


KINNEAR MOODIE

AND COMPANY LIMITED

**CIVIL ENGINEERING CONTRACTORS AND
SPECIALISTS IN TUNNEL CONSTRUCTION**

LONDON : 299-303 HITHER GREEN LANE, S.E.13.

GLASGOW : 180 HOPE STREET, C.2.



Circular tipping skips 2½ cu. ft. to 5 cu. yd.

ABELSON for SKIPS



Special and non-standard skips manufactured to your specifications.



Circular controlled discharge bottom dump skips ½ cu. yd. to 1 cu. yd.

Beltover skips ½ cu. yd. capacity.



Concrete pouring skip side discharge 10 cu. ft. to 27 cu. ft.



Boat skips 3 cu. ft. to 7 cu. ft.



Concrete pouring skips bottom discharge 10 cu. ft. to 27 cu. ft.

Square tunnelling or trenching skips 4-8 ft. cu. ft. capacity.



**PIN YOUR FAITH
TO THE TESTED
BRAND**

THIS LABEL ON
EVERY BARREL
CARRIES WITH
IT FIFTY YEARS'
EXPERIENCE OF
MANUFACTURE.

**NONE OTHER IS
"JUST AS GOOD"**

THE LEEDS OIL & GREASE CO.

Phone 22480


LEEDS, 10

'Grams: "Grease."

PADIHAM 'B'

Power Station

NEAR BURNLEY

*From the ground up . . .*

First the foundations, now the superstructure of the main power house and ancillary buildings. Gleeson have been entrusted with providing both base and backbone of the new Padiham 'B' Power Station near Burnley.

Work in hand or recently completed, includes the following Power Station contracts.

Consulting Civil
Engineers
C. S. Allott & Son,
Manchester 3

Consulting
Architects
Crutcher &
Seward,
Manchester


AGECROFT 'B'
CHADDERTON
FLEETWOOD
CARRINGTON
WAKEFIELD

DRAKELOW 'B'
HIGH MARNHAM
SELVEDERE
WILLINGTON 'B'

GLEESON

Central Electricity Generating Board,
Northern Project Group,
Agecroft Road, Pendlebury,
Manchester.

M. J. GLEESON (CONTRACTORS) LTD.
Haredon House, London Road, North Chesham, Surrey.
Tel: Fairlands 4321/8 lines.
LONDON • SHEFFIELD • MANCHESTER



A FIRST-CLASS SERVICE FOR ALL TYPES OF

REINFORCEMENT

DESIGN SUPPLY BENDING AND FIXING OF
MILD STEEL, COLD WORKED BARS AND
HIGH TENSILE FABRIC

WE ARE THE SOLE MANUFACTURERS OF

COROBAR

(TRADE MARK)

**THE COLD WORKED BAR
FOR
CONCRETE REINFORCEMENT**

OFFICES :

ARDSHIEL HOUSE
EMPIRE WAY
WEMBLEY, MDDX.




WORKS :


RIGBY LANE
DAWLEY ROAD
HAYES, MDDX.

**THE ENGINEERING DESIGN & CONSTRUCTION
COMPANY LIMITED**

TELEPHONE: WEMBLEY 9474 TELEGRAMS: EDCON WEMBLEY



CONSTRUCTIONAL PROJECTS AT HOME AND OVERSEAS



The Conon Valley Scheme in Scotland was built for the North of Scotland Hydro-Electric Board.

Consulting Engineers: Sir Alexander Gibb & Partners

Works in this scheme constructed by us include GLASCARNOCH DAM, illustrated above, VAICH DAM, LUICHART DAM, ACHANALT BARRAGE, with various associated Power Stations, Tunnels, Aqueducts, and Approach Roads.

CONTRACTS OVERSEAS—We are now building a new 1000-ft. span reinforced concrete bridge across the upper reaches of Sydney Harbour in Australia, and the new prestressed concrete Hobart Bridge in Tasmania across the Derwent River—length 4699 feet.


REED and MALLIK LTD

MILFORD MANOR
SALISBURY, WILTSHIRE

and

199 PICCADILLY, LONDON, W.1.

A member of the Reed Construction Holding Group



35-TONS PRECAST BRIDGE SECTION

We illustrate one of the 35-tons sections produced by Anglian Building Products Ltd., of Atlas Works, Lenwade, Norwich, and 67 Jermyn Street, London, W.1, for British Railways L. M. Region. Main Contractors: Leonard Fairclough Ltd.

WOODEN MOULD

was produced by

MAY & BUTCHER LTD

SPECIALISTS IN TIMBER SHUTTERS AND MOULDS FOR CONCRETE

More and more Contractors and Precast Concrete Makers in all parts of the country are taking advantage of the first-class service we offer in the supply of timber shutters and moulds to any design and size. This service has proved over and over again that by ordering your shutters and moulds from us you effect every possible saving in time, labour and money. However intricate the shutter or mould, you are assured of accuracy in every detail and a product with long trouble-free life. Shutters and moulds can be supplied with a plastic lining if desired. Full details of this class of work carried out by us are available on request.

HEYBRIDGE BASIN, MALDON, ESSEX.

TELEPHONE: MALDON 698/9



ORRIN MAIN DAM

In addition to the main Orrin Dam, shown above, other dams constructed by us for the North of Scotland Hydro-Electric Board include the Orrin Embankment Dam, and Meig Dam on the Canon Valley Scheme (Consulting Engineers: Sir Alexander Gibb & Partners), Dundreggan Dam on the lower Moriston Project, and Beannachron Dam on the Kilmorack and Strathfarrar Scheme (Consulting Engineers: Sir William Halcrow & Partners)

CONSTRUCTED BY

DUNCAN LOGAN
(CONTRACTORS) LTD.

CONTRACTORS FOR REINFORCED CONCRETE
CIVIL ENGINEERING AND BUILDING WORK

HEAD OFFICE: **MUIR OF ORD, ROSS-SHIRE**

TELEPHONE: MUIR OF ORD 275 (5 lines)

TRENTHAM GRAVEL COMPANY LIMITED

**supplied the concrete aggregates for
Kingsway Bridge over the Mersey**

**CONSTRUCTED BY
TARMAC CIVIL ENGINEERING LIMITED**


**PRODUCERS OF HIGH QUALITY
WASHED CONCRETE AGGREGATES**

We can supply materials graded to any requirement in
large or small quantities at economical prices for
contracts in

**STAFFORDSHIRE · CHESHIRE
SHROPSHIRE · LANCASHIRE**

HEAD OFFICE: LORDSLEY QUARRIES, WILLOUGHBRIDGE, MARKET DRAYTON, SHROPSHIRE
TELEPHONE: PIPE GATE 304
AND AT WILLOUGHBRIDGE QUARRY, NEAR WOORE, CHESHIRE

Underreamed boring
DOWN TO 110 FEET



with the
Mc KINNEY
Mobile Rig



If you would like further details, please write to:

McKINNEY FOUNDATIONS LIMITED

Manor Way, Boreham Wood, Hertfordshire. Telephone: Elstree 2854

A **LARGE** COMPANY

STORERS

WM. T. STORER & Co. LTD.

TIMBER IMPORTERS AND MERCHANTS

Established 1913



Sawing and Planing Mills:

RIVER ROAD, BARKING, ESSEX

Telephone: RIPPleway 0301 (10 lines)

FOR

SOFTWOOD

Top quality & service
Site investigations
Bored piling & Foundations
Materials & Structural testing



—Terresearch service has proved its worth —
 Terresearch specialists have a wide, practical experience
 in all branches of building and civil engineering,
 and full resources for carrying out investigations and
 research and sound speedy construction.

**WE HAVE SUCCESSFULLY CARRIED OUT
 SUCH WORK FOR:**

ATOMIC AND THERMAL POWER STATIONS · AIRFIELD WORKS
 RAILWAY WORKS · BRIDGES · ROAD WORKS
 MARINE AND HYDRAULIC WORKS · MULTI-STOREY OFFICES
 AND APARTMENTS · FACTORIES, etc.

OUR BROCHURE IS YOURS BY REQUEST

***T*erresearch LIMITED**

BUILDING AND CIVIL ENGINEERING LABORATORY
 PILING AND FOUNDATION ENGINEERS & CONTRACTORS

RUISLIP ROAD NORTHOLT GREENFORD MIDDLESEX Telephone: WAXlow 4341-3

CUT YOUR CONCRETE COSTS

with the

A.B. MOULD

MIXER-DRIVE SHOVEL

ALL-BRITISH DESIGN AND MANUFACTURE

(Patent applied for)

At last !

The perfect combination of a winch unit attached to and driven by the mixer, but operated from the press-button-controlled shovel.

THE BUILT-IN JIB ELIMINATES SITE INSTALLATION COSTS.



LOW CAPITAL OUTLAY RECOVERED IN TEN WEEKS
NO RUNNING COSTS
FITTED TO MOST MIXERS

Ask for a demonstration from :

A. B. MOULD & CONSTRUCTION CO., LTD.

VULCAN WORKS, VULCAN WAY
NEW ADDINGTON, SURREY

Telephone : Lodge Hill 2347

Telegrams : Abmould, Croydon




GIORRA DAM

Illustrated above, and Stronach Dam, part of the Breadalbane Hydro-Electric Works scheme, were constructed by us for the North of Scotland Hydro-Electric Board. Consulting Engineers: Messrs. James Williamson and Partners.



EDMUND NUTTALL SONS & CO. (LONDON) LTD. 22 Grosvenor Gardens, London, S.W.1

Why more and more contractors



IN BRITAIN Darex AEA was used throughout in the concrete construction of the Glendevon Dam



IN BRITAIN Darex AEA was incorporated in the bulk concrete of the North of Scotland Hydro Electric Board's Ait-na-Lairige Dam

***The first and foremost Air Entraining Agent**

***Used in the U.S.A. for more than 27 years on major projects**

***In use throughout the world**

Darex AEA is the original air entraining agent that has proved itself throughout the world for Dam Construction, Structural Concrete, Roads and Aerodromes, Bridges, Maritime Works and Concrete products. America, Belgium, Canada, Norway, Portugal, Sweden, Switzerland and many other countries acclaim Darex AEA as the first and foremost air entraining agent.

TECHNICAL SERVICE may be obtained from the sole U.K. distributors

EVODE OF STAFFORD

Are YOU using the EVODE PERSONAL SERVICE TO DESIGNERS? Write or phone for details.

EVODE LTD., (BUILDING CHEMICALS DIVISION) STAFFORD Tel: 2241 (5 lines)


torisk for Darex AEA

is the fifth ingredient for concrete

DAREX AEA, a ready-to-use, dark brown liquid, is an aqueous solution of triethanolamine salts of a sulfonated hydrocarbon. For smoother flow and finer finishing, it lubricates the concrete mix with millions of tiny air bubbles. It also contains a catalyst which promotes more rapid and complete hydration of portland cement. Not a resin or by-product, DAREX AEA is a chemical formulation manufactured to insure predictable performance. It is harmless and neutral and requires no pre-mixing with corrosive chemicals or water. DAREX AEA is ideally suitable for ready mixed concrete, structural concrete, mass concrete construction, concrete road construction, repairs and patching and concrete products.

- Air bubbles guard against frost damage and cracking even with repeated freezing and thawing.
- Makes concrete resistant to saline solutions, de-icing salts, sulphate and sea waters.
- Less mixing water can be used with no loss in slump.
- Improves placeability.
- Air bubbles lubricate and plasticize the mix.
- Minimizes bleeding, green shrinkage and segregation.

- Catalyst promotes faster and more thorough hydration, thus bringing out more of inherent strength of portland cement; ensures greater strength in both lean and rich mixes than non-catalysed air entraining agents.
- Will not entrain expensive air.
- Particularly effective with slag, lightweight or manufactured aggregates that tend to produce harsh concrete.
- Permits use of natural sand deficient in fines.



Reduce water with WRDA

WRDA, an aqueous solution of highly purified metallic salts of lignin sulfonic acid, is a ready-to-use, non-setting, dark brown, mobile liquid. It acts as a dispersing and plasticizing agent—makes possible easily placeable mixes with up to 20% less water content and a corresponding increase in strength and durability. It contains a catalyst which counteracts the normal hydration-retarding effect of dispersing admixtures; and a preservative. It is compatible with all known air entraining agents. WRDA does not require agitation, it comes ready-to-use.

- WRDA reduces natural interparticle attraction of cement grains and makes the mix more workable and placeable with less water.
- Gives low slumps without loss of placeability.
- Makes concrete flow cleanly around reinforcing steel and respond quickly to vibration, spading and compacting.
- Improves water retention and internal cohesiveness of the plastic mix.
- Cuts green and drying shrinkage.

- Reduces bleeding, honeycombing, water gain voids under aggregate and other segregation.
- Allows concrete floors to be finished sooner.
- Increases compressive strength up to 25%; also increases flexural and tensile strengths.
- The action on cement is physical. It does not change the chemical properties.
- Improves appearance of concrete by sharply reducing spalling, leaching and sand streaking.

AIR METERS AND DISPENSERS ARE READILY AVAILABLE

London Office: 82 VICTORIA STREET, S.W.1.

Tel: ABBey 4622 (3 lines)

9-W-143

NO. 15 IN A SERIES SHOWING TECHNICAL DEVELOPMENTS IN CONCRETE CONSTRUCTION

Prestressed concrete reservoir for New Zealand



Auckland Star photograph of the 4-million gallon reservoir under construction.

St. John's Reservoir, constructed for the Auckland City Council, is a circular prestressed concrete structure of four million gallons nominal capacity. The internal diameter is 180 ft., and the height from floor to underside of roof beams 25 ft. 8 in. Depth of excavation over the site averaged 7 ft. The reservoir is founded on firm clay. Further details of this unusual application are available on request.

Sponsor :
Auckland City Council.

Design :
Pre-Stressed Concrete (NZ) Ltd.

Construction :
Tapper Construction Ltd.


Johnsons were in at the start with wire for prestressed concrete. Their technicians worked with the Continental pioneers in the development of the technique, and today Johnsons wire is specified in a large number of prestressing contracts.

wire was essential -

Johnsons
of course!

Trumix 
CONCRETE

was used
for the
Kingsway
Bridge
on the new
Cheadle
By-pass




Kingsway Bridge over the River Mersey on the Cheadle By-Pass. Manchester City Surveyor: R. Nicholas, C.B.E., B.Sc., M.C.E., M.I.M.U.E., M.T.P.I. Manchester City Architect: Leonard C. Howitt, M.A.R.C.H., D.I.P.T.P., D.P.A., F.R.I.B.A. Consulting Engineers: Messrs. L. G. Mouchel & Partners. Contractors: Tarmac Civil Engineering Ltd.

Every day more than 600 cubic yards of Trumix ready-mixed concrete are produced at each of our five plants. Deliveries to any specification or guaranteed strength can be made at short notice by our large fleet of Mixer Trucks.

Leeds • Stockport • Bradford • Macclesfield • Glasgow

APHROSOL FC

for aerated concretes



Aphrosol FC is a foaming agent with the highest expansion compatible with foam stability.

It can be used in a conventional non-tilting drum mixer to prepare aerated concretes of dry density down to 75 lb/cu. ft.

Roofing screeds of aerated concrete made with Aphrosol are easy to lay, light in weight, and have good thermal insulating properties.

Aphrosol FC is equally suitable for the production of aerated mortar for use in the mechanical pointing of brickwork.

It is also of great value for the preparation of aerated mortars for injection grouting work in arresting slips or strengthening weak and unstable strata.

X73



Full information on request.

Imperial Chemical Industries Ltd London SW1 England



VINCULUM



A complete service

VINCULUM

...to the Architect



VINCULUM



and the Builder

VINCULUM


PRE-CAST CONCRETE

...for every purpose



TARMAQ VINCULUM LIMITED

ETTINGSALL WOLVERHAMPTON Telephone BILSTON 4101 (2 lines)



An Electrically Driven PC3 Concrete Pump with remixer. Capacities from 20 to 24 cu. yds. per hour. Ranges actually obtained 135 ft. vertical or 1,500 ft. horizontal. Also smaller model PC4—8-10 cu. yds. per hour.

EFFICIENT RECONDITIONING SERVICE

CONCRETE BY PUMP AND PIPELINE

- The most efficient method of placing concrete.
- Life of Pump practically indefinite: all essential surfaces in contact with concrete are renewable.
- Pumpable concrete must of necessity be good concrete.
- Pump and Mixing Plant can be located at the most convenient position within the pumping range.
- The continuous output of the Pump at a constant speed governs the working of the whole concreting gang.

THE REGISTERED TRADE MARK OF

PUMPCRET

THE CONCRETE PUMP COMPANY LIMITED

THE CONCRETE PUMP COMPANY LTD

4 STAFFORD TERRACE, LONDON, W.8

Telephone: Western 3546

Telegrams: Pumpcret, Kans, London



FRANKIPILE

**Large
Diameter
Bored
Piles**


YOUR INQUIRIES
ARE INVITED AND
WE WILL BE GLAD
TO ASSIST YOU
IN ANY MANNER

FRANKIPILE LIMITED • 15 VICTORIA STREET • LONDON • W.1

ONE...



TWO!



'STABIL' BINDERS

ARE GREAT LABOUR SAVERS

In one simple action they fix reinforcing rods as though welded. No slipping. No "fiddling" with wire. No tools to get mislaid. Any workman can use them. Made in all sizes for binding $\frac{1}{4}$ -inch up to $1\frac{1}{2}$ -inch rods. Give "Stabil" Binders a trial and judge for yourself.

- SEND TO-DAY for demonstration samples and prices.

HUNTLEY & SPARKS LTD

DEBURN RD., S. WIMBLEDON, S.W.19

Phone: Liberty 2446

WOOD MOULDS

for PRECASTING

EXTREME ACCURACY

ALL TYPES | ALL SIZES


25 years' experience at your service

ARCHITECTURAL SPECIALISTS
AND MODEL MAKERS

LAWS & SON (STAINES) LTD
(CONTRACTORS TO H.M. GOVERNMENT)

Langley Road Works, Staines, Middx

Telephone: Staines 53700



Trent Gravels

10,000 tons per week

Washed & Crushed $1\frac{1}{2}$ in. to $\frac{1}{2}$ in.

We are the leading suppliers of high-class concrete aggregates in the area shown above. Prompt deliveries guaranteed and keen competitive prices quoted. Send for samples and prices.

TRENT GRAVELS LTD


ATTENBOROUGH

Telephone: Beacon 54355

NOTTS

"CONCRETE SERIES" BOOKS ON CONCRETE

For a complete catalogue giving prices in sterling and dollars, send a postcard to:
CONCRETE PUBLICATIONS, Ltd.
14 Dartmouth St., London, S.W.1




can
be
Screw-fixed with a **RAWLPLUG**
FIXING DEVICE!

If you live to a hundred, you are unlikely to want to do much screw-fixing of eggshells! Yet this feat—possible only with a Rawlplug Fixing Device (a Rawinut)—does serve to highlight the astonishing effectiveness of these Devices in making 'difficult' and even 'impossible' fixings simple and straightforward. Whatever the screw or bolt fixing job, you'll save time, money and temper by using the appropriate Rawlplug Fixing Device.

RAWLPLUGS


The famous Rawlplug makes firm screw fixings in masonry in a mere fraction of the time taken by any other method. For all screw sizes up to 1" diam. coach screws.

**RAWLNUTS**


The amazing Rawinut forms its own 'rivet head' behind the material when screwed up from the front. Shakesproof and waterproof, it has many valuable uses in both building and manufacture.

**RAWLBOLTS**

For light or heavy bolting jobs. A dry fixing of enormous strength—no cold chiselling, no waiting for cement to harden. In all bolt diameters up to 1".

**SPRING TOGGLES**

For making firm fixings to such thin and structurally weak materials as plasterboard, ceilings etc. The wings of the device spring apart behind the material and spread the load over a wide area.


**GRAVITY TOGGLES**

Passed through a hole in hollow material, the long member falls into a vertical position by gravity, and is then drawn against the back of the material by screwing from the front.

**IMPOSSIBLE FIXINGS
ARE EASY WITH**



FIXING DEVICES For Speed and Strength!



For compacting mortar cubes
for compression tests to

B.S. 12/1958, 146, 1370, 915

Automatic Time Control

"CAPCO"

H.F. VIBRATOR

"CAPCO" CONCRETE TESTING APPARATUS also includes:
Cube Moulds; Slump Cones; Tensile, Vicat and Cylindrical
Moulds; Compacting Factor Apparatus—Standard and Auto-
matic; Sieve Vibrators and Sieves; etc.

CAPLIN ENGINEERING CO. LTD

ALPAX WORKS, ST. LEONARDS ROAD, WILLESDEN JUNCTION, LONDON, N.W.18

Phone: ELGAR 7191. Grams: CAPLINKO, London, N.W.10. Cables: CAPLINKO, LONDON

GUNITE SPECIALISTS

WM. MULCASTER

& CO. (CONTRACTORS) LTD.

We invite inquiries for Gunite Linings and Renderings
for new or old structures of every kind in any part
of the country.

HASLINGTON

CREWE

Telephone: Crewe 2265-4.

CONCRETE CONTRACTORS



on land

ENGINEERING AND REINFORCED



by the sea

BUILDING, CIVIL



from the air

...every aspect of advanced constructional design and practice was co-ordinated by Monk into the building of these three large projects—

Shell Administration Block, Stanlow;
Reconstruction of Hull Riverside Quay and South Side Albert Dock;
British Sealed Beams Ltd., new Factory, Corby.

Advanced techniques and broad experience keep Monk in the lead for swift economic construction, completed well within schedule time.

A. MONK & COMPANY LTD.

Monk

Warrington and London

Offices at: Hull, Middlesbrough and Stamford

LENSCRETE LTD

maximum light minimum cost


LITEX roof lights give a very high transmission of light—up to 92%—and are easily and quickly handled and fitted. A full range of standard form metal ventilators, curbs and liners are available for use with LITEX roof lights.



LITEX spherical roof lights


*Litex***LAMINATED FIBREGLASS
roof lights**

LITEX roof lights with their glass fibre reinforced construction can be used with advantage in many places where conventional lights would be impracticable or too costly. Virtually unbreakable, heavy packing is unnecessary allowing quick and easy handling on site.



LITEX rectangular roof lights

LITEX roof lights are ideal for use in schools, hospitals and other buildings where absolute safety is required—they will not shatter and cannot support combustion. The plastic will not creep, nor become brittle with age or very hot temperatures.




LITEX lantern lights


LITEX roof lights are not attacked by smoke or fumes from most industrial processes, and may safely be used in factory and workshop buildings.

For further information about LITEX roof lights please write to

LENSCRETE LIMITED Queens Circus London SW8 telephone MACaulay 1063

Bp**BOLTS & NUTS****TIE-RODS
ETC.****FOR THE
CONTRACTOR***Manufactured by***B. PRIEST & SONS LTD** OLD HILL STAFFS. ENG.

PHONE: CORLEY HEATH 6227 & 6228



POWER for industry

Our range of industrial engines are a practical proposition for many types of industrial equipment... compressors, cranes, pumps, contracting equipment, earth borers, generators, railcars, welding plant, works trucks, tractors and conversions. Simple design, modern flow-line production methods and common interchangeable parts contribute to the low cost of these high efficiency engines. And remember, every engine is fully backed by a World-wide Parts and Service Organi-

sation. Take your choice from a wide power range... Diesel 20 to 86 b.h.p. and Petrol 11 to 87 b.h.p. (12-hr. rating).

DIESEL ECONOMY—have you considered the replacement of existing power units in your equipment and trucks with the famous 4D Diesel engine? You'll have the unique advantages of economy, long-life and low running costs... plus the best service in the World!

Wherever you are, whatever your problem,



**MOTOR COMPANY LIMITED
ENGLAND**

are at your service

For further details of our

INDUSTRIAL ENGINES

and the equipment they power,
send the coupon to your nearest Ford Dealer
or direct to

FORD MOTOR COMPANY LIMITED · PARTS DIVISION (G51) · AVELEY DEPOT · SOUTH-WICKENDON · BOMFORD · ESSEX · ENGLAND

Please send me technical brochures of your
*PETROL/DIESEL Industrial Engines. The
maximum B.H.P. required is.....at.....
R.P.M. Also, please send details of the follow-
ing equipment powered by your engines.

Name

Address

Nature of Business

Telephone No.

* Delete where not applicable

G51-23-4



FOR REFERENCE

Cut out HACKING...

MULSIBOND, the tried and trusted key, will ensure a firm bond no matter how smooth the surface. Suitable for use on concrete, brickwork, glazed tiles, stone-work, etc.

multisibond

BONDER
for plaster and cement renderings.

Cut out

MOULD FACE TROUBLES...

with **MOLDCOTE**. Brushed or sprayed on, this new liquid treatment provides a smooth polished surface tough enough to withstand damage in everyday use. Will increase the working life of moulds, shuttering or formwork.

moldcote

SURFACE HARDENER
for moulds and shuttering.

Cut out

PRIMING TROUBLES...

by using **SURFILM** on Asbestos Cement, Hardboard or Bituminised surfaces. After application (just brush on) such difficult materials can be painted any colour.

surfilm

PRIMER
for difficult surfaces.

PRODUCTS OF



STUART B. DICKENS LTD.

Manor Way, Boreham Wood, Herts.
Telephone: Elstree 2211

Cut out this coupon now!

Please send leaflet giving full details of product I have ticked

MULSIBOND ☐ MOLDCOTE ☐ SURFILM ☐

NAME

ADDRESS

.....

.....

CCE

Eliminate propping and reduce labour costs with

Eliminate propping and reduce labour costs with

MILLS pecco-beam



The all-steel horizontal shoring which gives clear spans up to 27' 7"

- Proven safety factor 2.2:1
- Lightning adjustment from 8' 6" to 27' 7"
- Only two basic parts—easy to erect, store and transport
- Free work areas for kindred trades below
- High load capacity enables larger areas to be shuttered with fewer shores
- Rolled-in camber ensures level slab under load
- Plate section is 'V' shaped, so steel is doubled along length of beam
- Demonstrations arranged
- Immediate delivery from nearest MILLS depot
- Free planning and advisory service

For lighter loads and clear spans up to 21' 3", use the Lightweight pecco-beam.

For leaflets containing loading tables and full details of Standard and Lightweight PECCO-BEAMS get in touch with your nearest MILLS depot.

MILLS SCAFFOLD CO. LTD. (A subsidiary of Guest, Keen & Nettlefolds, Ltd.)

Head Office: Trussley Works, Hammersmith Grove, London W.6 (Riverside 3011)

Depots: BIRMINGHAM • BOURNEMOUTH • BRADFORD • BRIGHTON • BRISTOL • CANTERBURY • CARDIFF • COVENTRY • CROYDON • EDINBURGH • GLASGOW • HASTINGS • HULL • ILFORD • LEICESTER • LIVERPOOL • LONDON • MANCHESTER • MIDDLEBROUGH • NEWCASTLE • NOTTINGHAM • OXFORD • PLYMOUTH • PORTSMOUTH • PRESTON • READING • ROTTERHAM • SOUTHAMPTON • SWANSEA

THERE'S NO LIMIT TO THE SUPPORT YOU CAN GET FROM

MILLS



Bearing plates are drop forgings welded to beams. Drivewelded to avoid overlapping.



Unique wedge-lock secured at one corner allows

Ensure
safety
with

DORMAN LONG Steel Trench Sheeting

(Regd. Design No. 850,839)

The ideal for temporary lining,
easy to drive: can be used over and over again

PROMPT DELIVERY *Prices and full particulars on application to*

DORMAN LONG (Steel) LTD., SHEET DEPT., AYRTON WORKS, MIDDLESBROUGH
London Office: Terminal House, 52 Grosvenor Gardens, S.W.1



COPPER STRIPS

for expansion joints

All Reinforced Concrete Engineers recognise the advantages of using copper strips for sealing joints in concrete work. Copper is ductile, will not crack under repeated bending, is non-corrosive and is unaffected by wet concrete. We specialise in the supply of perforated copper strips of all required lengths and widths for expansion joints, and shall be pleased to submit prices against detailed specification.

ALEX J. CHEETHAM LTD.

MORTON STREET • FAIRFORTH • MANCHESTER

Telephone: FAIRFORTH 1115/6



DS.14

CONCRETE ROADS FIRST
because
CONCRETE ROADS LAST

REINFORCEMENT
by **McCALLS**

VICTORIA STREET, DERBY

City Engineer, M. L. Francis, F.R.I.C.S., M.I.Mun.E., etc.
12" concrete slab reinforced with two layers of 'Matobar' and topped with asphalt.

McCALL & COMPANY (SHEFFIELD) LIMITED

TEMPLEBOROUGH • SHEFFIELD • P.O. BOX 41

Telephone: ROTHERHAM 2076 (P.B. Ex. 8 lines)

LONDON: SLOANE 0428

PORTSMOUTH: COSHAM 78702

BIRMINGHAM: ACOCKS GREEN 0229

McCALL & COMPANY (SHEFFIELD) LIMITED

McCALLS MACALLOY AFRICA (PROPRIETARY) LIMITED

McCALLS MACALLOY LIMITED

McCALLS MACALLOY (AUSTRALIA) PTY. LIMITED

PRECISION ROOFS LIMITED

McCALLS MACALLOY (CANADA) LIMITED

SRB88

Testing concrete cubes on site


MILBANK-WELLS

HYDRAULIC PRESS AND CUBE MOULDS

Immediate Delivery

Two Sizes : 4 in. and 6 in.

PRESSES and CUBE MOULDS
Testing to 16,000 lb. per sq. in. to
B.S. 1881.



Approved for
all Government
Contracts

IN USE
ALL OVER
THE WORLD

6-IN. PRESS
258 TONS

£245

4-IN. PRESS
110 TONS

£125

MILBANK FLOORS LTD

PRESTRESSED CONCRETE CONSTRUCTION

RIVER HOUSE, EARLS COLNE, ESSEX

Telephone: Earls Colne 410



PRESTRESSED FLOORS & ROOFS SPANS UP TO 40 ft. FRAME BUILDINGS ALL TYPES



THE MOST ADAPTABLE FRAME BUILDING
FOR INDUSTRY AND AGRICULTURE

SINGLE SPAN · MULTI SPAN · CANTILEVER



42" diameter to 27" diam ter straight back mould for manhole tapers

Moulds and formwork

for the concrete industry

A service to the industry ranging from the small equipment illustrated to complete spinning plants, backed by years of technical experience.

We are now operating from our extensive new premises at the address below.

Further details and quotations sent on request

Coneybeare

THE ORIGINAL PIPE MOULDS


Coneybeare & Co., Ltd., Torrington Road, Ashford, Kent. Telephone: Ashford 1545.

**CONCRETE
P ROOFING
Co. LTD.**

**GUNITE
SPECIALISTS**

Expert advice and schemes submitted for gunite work of every kind. Complete information on the various uses of gunite will be gladly sent on request

116 Richmond Road, Kingston-upon-Thames, Surrey. Telephone: KINGSTON 7883 and 9251



Tel.: UXBRIDGE
3399

T.P.S. SHUTTERING and MOULD PAINTS

will make your shuttering and moulds last longer,
often save the labour costs of repeated mould oil
application, and are also the cheapest alkali
primers for general use under paint work

*Reduced costs and clean concrete surfaces are always obtained from shutters and
moulds treated with these paints. Wood grain is filled and sealed against water and
alkali. Douglas Fir staining eliminated*

Ask for the type for YOUR purpose
**SPECIAL TYPES FOR PLYWOOD,
STEEL OR CONCRETE SURFACES
TO SUIT ALL REQUIREMENTS**

PROMPT DELIVERY FROM STOCK!

TECHNICAL PAINT SERVICES, DEPT. C.C.E.
THE PAINT CENTRE — UXBRIDGE — MIDDLESEX

***If you want to pre-tension
economically and efficiently —
consult the specialists in this field***


**WIRE AND STRAND GRIPS
PLAIN AND SPRING-LOADED**

**HYDRAULIC RAMS
25 TO 200 TONS CAPACITY
3' TO 36' EXTENSION**

**HYDRAULIC HAND AND
POWER PUMPS TO SUIT
ALL RAM SIZES**

**UNIVERSAL PULL-CARRIAGES
FOR MULTIPLE STRESSING
IN UNITS OF 50, 100
AND 150 TONS**

**STRESSING BED DESIGNS
SUPPLIED FREE WITH ALL
EQUIPMENT ORDERS
COMPLETE PLANT LAYOUTS
UNDERTAKEN BY ARRANGEMENT**



SEND FOR BOOKLET AND PRICE LIST TO

STRESSING DEVELOPMENTS LTD.

95 KINGSTON HILL, KINGSTON-UPON-THAMES

TELEPHONE: KINGSTON 2372

"COL-O-ROCK"

Registered Trade Mark

EXPOSED-AGGREGATE PANELS

by

J. A. KING & Co., LTD

Write or Phone

181 Queen Victoria St., LONDON, E.C.4

Telephone: CENTral 5866 (5 lines)

Telegrams: Kinovique Cent London

WELBECK TRADING Co. (London) Ltd

WELBECK HOUSE, 2-6 BACHES STREET, CITY ROAD, LONDON, N.1

Telephone: CLErkenwell 4373 (PBX)

Telex: 23712

STEEL REINFORCEMENT MANUFACTURERS

DIAMETERS $\frac{1}{8}$ " to $1\frac{1}{2}$ "


Cut to dead lengths a speciality

No extra for cut lengths over 5 feet

BENDING if required

EARLY DELIVERY

Write or telephone your requirements



Precision in Concrete Cover...




Write Now!

←
for fully
illustrated
brochure

A revolutionary economy
for lightness, speed of
handling, and range of
application—for reinforcing
bars in concrete.

with



PATENTED. Regd. Design 893503.

Plastic Distance Pieces

Samuel & Son (moulders) Ltd

WREN MILL, CHADDERTON, LANCs. Sales Office: Tel.: Manchester DEA 4671/2

Sole Manufacturers and Distributors of ABIT pk Plastic Distance pieces (A.B.
ABERG No. 31269/58) in Great Britain, The Commonwealth and Eire.



Architects:
S. N. Cooke & Partners
F./P.R.I.B.A.

Main Contractors:
William Tomson & Sons
Ltd., Bolton.

Maxweld reinforces it

The reinforcement fabric used in the Metal Box Company factory at Bolton was supplied by Richard Hill. Do you need reinforcements? Then call up the Maxweld man! He can give you all the facts on the type and quantity of fabric you'll need plus a rough idea of the cost. And he's backed by the

Richard Hill Design Service

who can then draw up more detailed plans and estimates. You can get him at Middlesbrough (2206), London (Mayfair 3636), Birmingham (Mid. 6625), Manchester (Central 1652), Leeds (2-7540), Bristol (24977), Glasgow (Central 2179), Nottingham (Bulwell 27-6383), Bournemouth (Westbourne 63491), Cardiff (46552), Belfast (26126).

Maxweld fabric

is manufactured by **RICHARD HILL LIMITED** (Established 1888)


Newport Wire and Rolling Mills, Middlesbrough, Yorkshire. Tel: Middlesbrough 2206

A MEMBER OF THE FIRTH CLEVELAND GROUP



CBS 11W X

Colcrete GROUTED CONCRETE in BRIDGE CONSTRUCTION



WORLD'S LONGEST SUBMERSIBLE BRIDGE

Work is nearing completion on this 2,434 ft. long reinforced concrete bridge which will carry the Bombay-Agra road between Gwalior and Dholpur over the river Chambal. The bridge is 24 ft. wide between kerbs.

Foundations, piers and fill-over spandrels in Colcrete.

The Contractors are Messrs. Gammon India Private Limited.



Enquiries to:—

COLCRETE LTD

GUN LANE, STROOD, KENT

Telephone: Strood 78431/2/3.

The first thick homogeneous fibreboard expansion joint filler
made in Great Britain

PD RESILEX

Complies with Air Ministry Specification 20138 - Part III Class 030.

Road and Runway grades of approved sealing compound available on request.

Standard Sizes

Thickness: 1", 1½", 2", 3", 4", 5", 6", 8", 10".
Lengths: 4', 5', 6', 7', 8', 9', and 10 feet.
Widths: From 2" to 48"
Special sizes and shapes to order.

... also available in 1", 1½", & 2" thicknesses

The first British made 100% wood fibre expansion joint filler manufactured entirely from home produced materials which has many unique advantages wherever concrete is used.

It is impregnated by a new solvent injection process with a low volatile high residual binder guaranteeing saturation of all fibres.

It will not disintegrate when wet because of its water resistance and high wet strength.

Resilex is not laminated or otherwise fastened together; it is embedded by road and runway grade of sealing compound and can be delivered in pre-cutted slabs. Fully descriptive leaflet on request.




POWELL DUFFRYN TIMBER INDUSTRIES LIMITED
Queensferry, Chester

Telephone: Hawarden 2001/4




Bridge Bearings by WESTWOODS




Universal Bearings to support 250 tons, allowing for horizontal movement in all directions, and with vertical adjustment. The illustration shows two Bearings, one with grease casings removed.


OTHER TYPICAL TYPES :—




DOUBLE-ROLLER
EXPANSION BEARING



THREE-ROLLER EXPANSION BEARING



HEMISPHERICAL
BEARING



SINGLE-ROLLER
EXPANSION BEARING



FIXED-ROCKER
BEARING

Contractors to H.M. Government Departments.
Crown Agents for the Colonies. British Rail-
ways (British Transport Commission) etc. etc.
Bridge and Constructional Engineers, Manu-
facturers of Mechanical Grabs, Pressed Steel
Troughing and Sheet Metal Equipment. Steel
Stock Holders.

JOSEPH WESTWOOD & CO. LTD.
NAPIER YARD, MILLWALL, LONDON, E.14 Phone : EASt 1043

*Grams: Westwood, Eastphone, London. Cables: Westwood, London.

BRITISH VISQUEEN

make a No.

choice



The new British Visqueen factory at Stevenage was built to produce the largest output of polythene sheeting in Europe; and it is here that the Visqueen Building sheet is also manufactured to supply an increasing number of applications for it in the building industry.

To render the concrete factory floors hard, dustless, waterproof and able to withstand exceptionally heavy wear and tear, British Visqueen chose Lillington's No. 1 Metallic Liquid.

For nearly fifty years, architects have specified Lillington's No. 1 Metallic Liquid, the scientifically prepared admixture that renders concrete completely waterproof and dustless and accelerates setting time.

No. 1 Metallic Liquid is a necessity for waterproofing cement renderings to walls and basements, in mass concrete retaining walls, foundations, flat roofs and tanks. You can rely on it to give complete satisfaction because IT IS THE ONLY PROOFER SOLD UNDER GUARANTEE.

LILLINGTON'S
No. 1 Metallic Liquid

From **5/-** per gallon

Special terms for
bulk contracts

Write for Booklet 56

ALL OUR PRODUCTS NOW SOLD IN FREE CONTAINERS

GEORGE LILLINGTON & CO. LTD

Willow Lane, Mitcham, Surrey. Tel: Mitcham 1066. For Scotland: 41 High Street, Greenock

AP/339A



HUMDINGER

RELIABLE high-frequency vibrators



SLOW SPEED DRIVE:

FLEXIBLE SHAFT
RUNS AT 2,850 R.P.M.
LESS MAINTENANCE
LASTS LONGER

12,000 VIBRATIONS PER MINUTE:

THOROUGH COMPACTION
OF COARSE MIXES.
HIGHEST DEGREE OF
DENSITY

INTERCHANGEABLE HEADS:

1" DIA. x 25" LONG
1 1/2" " x 22" "
2 1/2" " x 19 1/2" "
3" " x 15" "

USEFUL ACCESSORIES:

GRINDING AND
CLEANING TOOLS
FOR A VARIETY OF
USES

OTHER MODELS IN THE POPULAR RANGE OF ACE CONSTRUCTION EQUIPMENT. "Skymaster Mk. II"—Man-carrying hoist. "Loadmaster"—Concrete Elevator. "Bomag"—Vibrating Rollers. "Comet"—Mobile Hoist. "Dalli"—Handscraper.

ACE SERVICE: "Service to the Customer", that's the key phrase of the ACE Service Department, unrivalled for its courtesy, efficiency and speed.

The photograph used in this advertisement was taken by kind permission of W. J. Simms, Sons & Co. Ltd.



A.C.E. MACHINERY LIMITED

**WATERTIGHT
LININGS
FOR
RESERVOIRS,
SWIMMING
POOLS, ETC.**



**LININGS
FOR
TUNNELS,
SEWERS,
TANKS.**

*Specialists in the Repair and Reconditioning of
Reinforced Concrete Structures, etc.*

THE

GUNITE
CONSTRUCTION CO. LTD
WESTERN HOUSE, HITCHIN, HERTS.

Telegrams :
Gunite
Hitchin

Telephone :
Hitchin
4371

**Best Quality
CONCRETE
AGGREGATES**
in all grades

DELIVERED BY ROAD OR RAIL

**WM. BOYER
& SONS LTD**

MEMBERS OF S. & G.A. of G.B.

ESTABLISHED 1810

IRONGATE WHARF, PADDINGTON, W2

TELEPHONE : PADDINGTON 2024-6

**TABLES FOR THE DESIGN OF BEAMS AND
SLABS ACCORDING TO B.S. CODE OF PRACTICE
No. 114, 1957**

In response to many requests, the article and tables by Mr. Jacques S. Cohen, in this journal for August, 1957, have been reprinted together with an additional table. These tables enable any rectangular section to be quickly designed by both the elastic method and the load-factor method, and the relative economy of the results of each method of design can be seen at a glance. The price of the reprint is 4s. (4s. 3d. by post); 1 dollar in Canada and the U.S.A.

CONCRETE PUBLICATIONS, LTD., 14 Dartmouth Street, London, S.W.1

PERFECT-SIMPLEX

FOR REINFORCING BARS







PERFECT—From Hooks to Angles

without re-setting control pins, by means of selector lever.

Double Bends performed in one operation by use of

bending arm. Attachment for bending batches of stirrups.

Attachments to meet special requirements can be supplied for each model in Perfect range.



SIMPLEX—High speed return of cropping head facilitates accurate dimensions of bars whilst maintaining high output. Selection of intermittent or continuous cutting by hand lever.

Various sizes in both Perfect and Simplex ranges to cater for maximum bar dimensions.

"INFORMATION WITH PLEASURE"

WOOD, PRITCHETT & PARTNERS LIMITED

20-22, Hammermith Broadway, London, W.8. Cable: Hecquip, London. Telegram: Marbup, London, W.8. Telephone: Riverside 2224 5, 6



Steel Reinforcement

A complete service of
Design, Fabrication and
Fixing of Steel Rein-
forcement for all types
of Reinforced Concrete
Construction.

M.S. Bars to B.S.S. 785, bent,
bundled and labelled, delivered to site
ready for fixing. No loss of time in
checking and sorting material. No
loss of material due to prolonged
storage on site.

T. G. JONES

AND COMPANY LIMITED

REINFORCEMENT ENGINEERS

17 BUCKINGHAM PALACE GARDENS
LONDON, S.W.1 Tel: 5L0ane 5271

Head Office: Wood Lane, London, W.12

Tel: Shepherds Bush 2020

South Wales Office: Bute Street, Cardiff
Tel: 28786

Works: Shepherds Bush, London. Neasden, Middx.
Treorchy, Glam.



COMPRESSION TESTING MACHINES



MODEL T1E PORTABLE COMPRESSION TESTING MACHINE

for site testing concrete cubes, cylinders, etc.

- Ideally suitable for use on construction sites.
- Easily portable—weighing only 3½ cwt.
- Compact—less than three feet high.
- Capacity 150 tons by increments of ½ ton.
- Convenient controls including load pacer.

This latest development in our range of Compression Testing Machines incorporates a unique and patented method of load measurement.

Two gauges indicate the load exerted on the specimen by measuring the magnified elastic deformation of the frame of the machine. An integral load-pacing device enables tests to be performed at constant rates in accordance with B.S.S.1881. It is the completely ideal portable Compression Tester.

MODEL T1A/MC COMPRESSION TESTING MACHINE

for testing concrete cubes, cylinders, bricks, etc.

A first-class machine with capacities from 100 to 300 tons, the T1A/MC comprises a Loading Unit and a Console which can be arranged to suit individual needs.

The Loading Unit is rigid, robust and easily accessible from all sides. An almost pulsationless oil pump ensures smooth loading. A Load-Pacer can be fitted for loading at a constant and pre-determined rate.

The Console houses the load gauges, pumping unit and controls. Its remoteness from the loading unit minimises shock to the loading gauges.


The design, craftsmanship, and outstanding performance of this machine are the result of nearly 90 years of experience in testing machine manufacture.

We shall be pleased to supply further details on request.



SAML. DENISON & SON LTD
HUNSLET FOUNDRY-MOOR ROAD-LEEDS 10

Tel: Leeds 7-5488 Grams: 'Weigh Loads 10'



Area Offices at **LONDON**
St. Ouen 4628

MANCHESTER
Blackfriars 1986

BIRMINGHAM
Midland 3931

LEEDS
Leeds 2-8433



Model VP 350-A (Swivel Base or Barrow Mounting)

Prompt Delivery. Highly Competitive Prices. Genuine Service. Re-Sale Terms Available.

* We operate a 48-hour Shaft Repair Service for all makes. Write to-day for 8-page fully descriptive Catalogue. Agents throughout the world.

30 years' experience in the design and manufacture of flex-shaft tools.

THE FLEXIBLE DRIVE & TOOL CO., LTD.

EDENBRIDGE, KENT. Telephone: 3385-6

LONDON OFFICE: 17 QUEENSBERRY WAY, S.W.7. Telephone: KENsington 3583

For Greater Strength, Firmer Bonding
and Better Surfacing of Concrete—

"BAXTUL"

Regd. Trade Mark

British Made

Extra-High Frequency

INTERNAL CONCRETE VIBRATORS

● The model illustrated here operates at 9,000 to 15,000 Vibrations per minute from low flexible shaft speeds of 4,500 to 7,500 R.P.M.

● Petrol or Electric Drive.

● Robustly built throughout and backed by genuine service.

● Fitted centrifugal clutch, long-life flexible drive and Vibrator.

This unique machine, with quick-change additional tools, can also be used for: SURFACING, WET-RUBBING CONCRETE, GRINDING, DISC SANDING, AND DRILLING (up to 1½" in Concrete, 1" in Steel, and 2" in Wood).

"Steel Reinforcement: Cutting, Bending & Fixing"

By L. A. DISNEY


A practical work by a thoroughly experienced author. 100 illustrations from actual work. Chapters include: (1) The reasons for reinforcement; (2) Types of reinforcement; (3) Ordering the steel; (4) Unloading, sorting and stacking; (5) Arrangement of plant on the site; (6) How to read working drawings and bending schedules; (7) Methods of cutting bars; (8) Methods of bending; (9) Methods of fixing. Many hints and tips from practical experience.

64 pages. Price, 6s.; by post, 6s. 7d.

\$1.50 in North America.

CONCRETE PUBLICATIONS LTD.

14 DARTMOUTH ST., LONDON, S.W.1



...every day—somewhere—some roofs
are waterproofed with the



BUILT UP ROOFING SYSTEM

- * Any roof can be treated
- * Applied cold without preliminary treatment
- * Used and proved for over 25 years
- * Foreman Demonstrators are available to assist your own workpeople, or, if you prefer, our contracts department can undertake the work for you and provide free maintenance.

A PRODUCT OF



OF STAFFORD

ROOF WATERPROOFING · CONCRETE ADMIXTURES AND HARDENERS
PROTECTIVE PAINTS AND BITUMINOUS COATINGS · GAP AND
JOINT SEALING MASTICS AND GUN · INDUSTRIAL ADHESIVES

* **SEND FOR LITERATURE** Evode Ltd., (Building Chemicals Division) Stafford. Phone: 2241 (6 lines)
London Office: 82 Victoria Street, S.W.1. Phone: ABBey 4822 (3 lines)

B.W.111

means 4

MACALLOY

NEW RELIABILITY

'Macalloy' high tensile bars used in the Lee-McCall system of prestressing concrete offer the utmost reliability and accuracy of stressing.

The robust end plates are positively and accurately secured without possibility of distortion.

The rolled thread gives a positive non-slip anchorage.

Anchorage can be checked for stress up to the time of grouting.

The jacking equipment used enables easy and accurate measurement of extension and the force can be verified on a large gauge.

The large diameter Macalloy bars are more resistant to corrosion than mild steel.

The small couplers do not obstruct grout flow, and grouting is reliable and trouble free.

McCALLS MACALLOY LIMITED

TEMPLEBOROUGH · SHEFFIELD · P.O. BOX 41

Telephone: ROTHERHAM 2076 (P.B. Ex 8 lines)

LONDON: SLOANE 8428

PORTSMOUTH: COSHAM 78782

BIRMINGHAM: ACOCKS GREEN 0219

PRESTRESSING
BY McCALLS

McCALL & CO (SHEFFIELD) LTD

McCALLS MACALLOY AFRICA (PROPRIETARY) LTD

McCALLS MACALLOY LTD

McCALLS MACALLOY (AUSTRALIA) PTY. LTD.

PRECISION ROOFS LTD.


McCALLS MACALLOY (CANADA) LTD.

HILTON GRAVEL

SEVEN
PITS

250
LORRIES

8,000
TONS
PER DAY



FOR QUALITY & SERVICE

REGULAR DELIVERIES THROUGHOUT

STAFFORDSHIRE

• CHESHIRE

DERBYSHIRE

• NOTTINGHAMSHIRE

WEST RIDING

• LANCASHIRE

SHROPSHIRE

• WARWICKSHIRE

LEICESTERSHIRE

• RUTLAND

READY
MIXED
CONCRETE

20 miles radius
MANCHESTER

From our Plant
at


RICE STREET
MANCHESTER 3

DEAnsgate 5455

The illustration above shows one of our seven pits equipped with the most modern washing and grading plant for producing concrete aggregates that will satisfy the most exacting requirements for cleanliness and grading to specifications.

HILTON GRAVEL LIMITED

HEAD OFFICE: HILTON, DERBY. Tel: ETWALL 422




THE P.C.4 PUMPCRET CONCRETE PUMP

CONCRETE BY PUMP AND PIPELINE

Specifications:

Two Sizes	P.C.3	P.C.4
Capacities per hour, approx. . . .	20-24 cu. yd.	8-10 cu. yd.
Range:		
Horizontal, approx.	1500 ft.	1250 ft.
or Vertical, approx.	135 ft.	125 ft.
Pipeline	6" i.d.	4 1/2" i.d.
Power required: Electric or Diesel	45 h.p.	25 h.p.

FOR HIRE



THE REGISTERED TRADE MARK OF
THE CONCRETE PUMP COMPANY LIMITED

PUMPCRET HIRE COMPANY LTD

4 STAFFORD TERRACE, LONDON, W.8

Telephone : Western 3546.

Telegrams : Pumpcret, Kens, London

WHY Sealocrete

AEA

makes the **best** concrete ...

Sealocrete Air Entraining Agent in concrete mixes **IMPROVES** flow, compaction and impermeability of concrete; resistance to sulphate and frost attack; pumping without segregation; coverage of reinforcement; density and smoothness; workability; riding qualities of concrete roads.

REDUCES water-cement ratio; vibrating and placing time by half; segregation and bleeding; wear on mixing and placing plant; green breakages and gives sharp corners; manufacturing costs.

SEALOCRETE PRODUCTS LIMITED

ATLANTIC WORKS · HYTHE ROAD · LONDON N.W.10

Telephone: Ladbroke 0015/P.B.E.

Telegrams and Cables: Sealocrete. Wesphone, London



Only the best is good enough

SELSET RESERVOIR FOR TEES VALLEY AND CLEVELAND WATER BOARD

Concrete incorporating Sealocrete Air Entraining Agent pumped approximately 1200 feet through re-mixer up hillside.

Contractors: Balfour Beatty & Co. Ltd.

Consulting Engineers: Edward Sandeman, Kennard & Partners.



FOR CONCRETE PRODUCTS



Invest in

RANALAH

STEEL
MOULDS

CUT CAPITAL COSTS
BETTER CASTS & MORE
CASTS PER MOULD



GARAGES, COAL BUNKERS, CILLS,
COPING STONES, AGRICULTURAL AND
INDUSTRIAL BUILDINGS, FENCING POSTS,
KERBS, GARDEN EDGING, ETC.



RANALAH STEEL MOULDS LTD

LOWER BEVEDEAN

BRIGHTON

SUSSEX TEL: 62216-78


ALL-BRITISH



HYDRAULIC BAR CROPPERS



FOR SALE
OR HIRE



for Reinforced Concrete Contractors

The Standard Bar Cropper, illustrated on the left, has a capacity ranging from one 1½-in. bar to eight ½-in. diameter or smaller bars, including rounds, squares and flats.

for Precast Concrete Makers

The small model, also illustrated, is specially designed to meet the requirements of the precast concrete maker. Its capacity includes one 1-in. bar down to multiples of smaller diameter bars, including rounds, squares, and flats.

E · P · ALLAM & CO. LTD.

LONDON: 132-135 Sloane Street, S.W.1.

Telephone: Sloane 9976 (5 lines)

Works: Southend-on-Sea Tel.: Eastwood 525243

AGENTS & DISTRIBUTORS: Strangford Ltd., Belfast and Dublin; A. Gunn & Co. Ltd., Altrincham, Chas.; O. L. Davies Ltd., Port Talbot, Glam.; J. Lewis (Machinery) Ltd., Burslem, Stoke-on-Trent; G. B. Corner & Son, Leeds and Nottingham; John Haulstone Ltd., Newcastle-on-Tyne; W. R. Selwood, Ltd., Chandler's Ford, Southampton; J. A. McAra & Co. Ltd., Glasgow.

The most popular portable bulk cement Silo in the world



The *New* P TYPE PORTASILO

Silos from £365

The only complete range of equipment

Laminated wood body for ideal storage of cement

Fully automatic, press-button operation if required

Rugged steel base to withstand the toughest site conditions

Fullway weighing equipment - proved on thousands of sites

Backed by unrivalled after-sales service

Also available for HIRE

PORTASILO

LIMITED

HOME SALES OFFICE:

LAWRENCE ROAD GREEN LANE HOUNSLOW MIDDLESEX Telephone: HOUNSLOW 6452/3

HEAD OFFICE: YORK and at BIRMINGHAM - MANCHESTER - GLASGOW - BRISTOL - BELFAST and DUBLIN

CONCRETE AND CONSTRUCTIONAL ENGINEERING

INCLUDING PRESTRESSED CONCRETE

Volume LV, No. 4.

LONDON, APRIL, 1960.

EDITORIAL NOTES

Concrete in the Gas Industry.

THE growing importance of civil engineering in the gas industry was emphasised in some of the papers presented to the International Gas Conference held in Rome recently. A representative of one of the British Gas Boards indicated the extent to which recent developments in civil engineering, and in concrete in particular, are used in structures associated with the production, storage, and distribution of gas, and also described how the British gas industry is applying knowledge gained in other industries and how these developments have been applied in ways that sometimes are new, such as site investigations, precast and prestressed concrete, and the foundations of vibrating machinery. In foundation construction, methods have been developed whereby work such as sheet-piling, which is generally a temporary provision, is incorporated as part of the permanent works. New methods of testing piles have also been investigated.

The cost of the foundations and other civil engineering works at the older types of gas-works may have been as much as 25 per cent. of the total cost, but in some of the more modern methods of making gas the cost of the civil engineering work is a smaller proportion of the total. A major requirement in civil engineering works at gas-works is resistance to corrosion by the atmosphere and the ground. For this reason one of the earliest applications of reinforced concrete was to replace steel for many such works. Although steel plates are still commonly used for gas-holders, it is interesting to note that fifty years ago a non-telescopic gas-holder in Germany was constructed completely of reinforced concrete and was described in this journal at the time. The first gas-holder tank of reinforced concrete in Great Britain was built about 1902 at Hampton Court.

Many gas-works are on sites where the ground has little strength and therefore the cost of foundations is an important proportion of the total cost of the civil engineering works. Because steel structures are lighter in weight the foundations for such structures are less costly, but the greater cost of maintenance of steel has resulted in the use of reinforced concrete superstructures where practicable, in spite of their greater weight. The virulent conditions that exist at gas-works, however, have sometimes resulted in the spalling and subsequent deterioration of reinforced concrete a few years after its construction. The advent of prestressed concrete was therefore welcomed by the gas industry because it enables a structure to be as much as 25 per cent. lighter in weight than one built of reinforced concrete,

and, if it is well designed, it is free from cracks which are commonly the first cause of deterioration of reinforced concrete. Even if prestressed concrete were more expensive than reinforced concrete, and this is not always the case—especially if the lower cost of the foundations is taken into account—the gas industry is likely to use prestressed concrete because of its greater durability in polluted atmospheres, and many prestressed structures have been and are being built at gas-works. It has been claimed that some of these structures or their components recently built in Great Britain are the first of their type: for example, it is thought that the first prestressed piles in Great Britain were driven in connection with a gas-holder tank at Stanford-le-Hope as reported in this journal for May, 1950. Prestressed concrete is also particularly suitable for the ring-beams of gas-holder tanks. In the past the crown-framing in such tanks was built in steel, but reinforced concrete, and more recently prestressed concrete, have been used for this purpose. There is already sufficient experience to show that fully-prestressed concrete is more resistant to corrosion than reinforced concrete, and the experience on railways suggests that the same may be said of concrete members that are partially prestressed. Thin concrete slabs as are usual in "shell" roofs are not particularly suitable at gas-works because of the thin cover of concrete over the steel. Thin slabs have, however, been used for the roofs of buildings at gas-works and chemical works but protection is necessary to ensure durability.

New developments such as the importation of methane, the gasification of certain products from oil refineries, German processes now in use in Great Britain for the complete gasification of coal, and a new British system of hydrogenation, may give the gas industry a new lease of life, particularly as the cost of distributing gas is very much less than the cost of distributing equivalent amounts of energy in the form of electricity. Some of the new methods of making gas require civil engineering works of types not formerly used at gas-works, although in general they may require less civil engineering work. Small bases only are required for the main plant used in the new processes, but water towers and chimneys may be required for auxiliary processes and the importation of methane would require jetties or wharves and large insulated storage tanks. Civil engineering activities are also likely to result from recent developments such as the investigation of the practicability of underground storage and proposals to centralise production.

In the case of the hydrogenation and other processes incorporating an oxygenation plant, extremely low temperatures are experienced. There is little data available regarding the behaviour of concrete at low temperatures. Research at the University of Ghent has shown that at a temperature of minus 40 deg. C. the crushing strength and modulus of rupture of concrete increases considerably, as does the ultimate strength of a beam, and that, consequent upon the increase in the elastic modulus, there is less deformation. At this temperature mild steel becomes brittle but, even at temperatures as low as that of liquid nitrogen (about minus 200 deg. C.), data from U.S.A. sources show that high-tensile steel seems to suffer little loss of strength or ductility. The temperature in some of these new plants may be below minus 150 deg. C., and in the present state of knowledge it may be advisable to insulate the concrete so that it is subjected only to temperatures at which its behaviour is predictable. Such insulation would also reduce the stresses due to differences of temperature, and avoid the possibility of unknown phenomena which may occur at very low temperature.

The Analysis of Symmetrical Single-bay Multiple-story Frames.

By K. BRZEZINSKI.

For any arrangement of loads, a single-bay multiple-story frame which is symmetrical can be analysed by the moment-distribution method using two operations only, namely one for the symmetrical component of the load and the other for the asymmetrical component. It is necessary to calculate the moments for only half the frame, usually the part to the left of the axis of symmetry.

Symmetrical Loads.

For symmetrical loads the stiffness of any beam is $K_b = \frac{2EI}{L}$, the stiffness of a column with both ends fixed is $K_c = \frac{4EI}{L}$, the stiffness of a column with one end hinged is $K_c = \frac{3EI}{L}$, and the carry-over factor is $C = +\frac{1}{2}$.

The fixed-end moments for most common arrangements of loads on beams are given in text books and it is assumed that the method of moment distribution is known. The sign conventions for external loads are that vertical loads are positive when acting downwards, that horizontal loads are positive when acting from left to right, and that moments are positive when acting clockwise. The moments for one half of the frame will be of opposite sign to the moments for the other half.

Asymmetrical Loads.

(1) FRAMES WITH VERTICAL COLUMNS ONLY.—The stiffness of a beam is $K_b = \frac{6EI_b}{L_b}$, the stiffness (defined as the moment required at the free end of the column to rotate it through unit angle, while the other end remains fixed) for each end of a column with both ends fixed is $K_c = \frac{EI_c}{L_c}$, but for the top of a column which is hinged at the bottom $K_c = 0$. The carry-over factor for columns is $C_c = -1$; there is no carry-over factor for beams or for the hinged end of a column.














The fixed-end moments for the asymmetrical component of the load on a beam are given in tables, or can be calculated directly from the fixed-end moments M_A and M_B produced on a beam AB by the total load.

$$\text{For symmetrical loads, } M_A' = \frac{M_A + M_B}{2}$$

$$\text{For asymmetrical loads, } M_A'' = \frac{M_A - M_B}{2}$$

The fixed-end moments for the columns are calculated on the assumption that the top of the column is fixed against rotation only and is free to move horizontally. The column acts as a cantilever, and the moments for common

TABLE I.—LOAD FACTORS FOR CANTILEVERED BEAMS.

1	2	3	4	5	6
	F.E. Moment M_A	Type of loading 	Rotation θ_B	Deflection y_B	
0	$-M$		$+\frac{NL}{EI}$	$+\frac{NL^2}{2EI}$	$-M$
$-M \cdot \frac{6}{L}$	$-M$		$+\frac{Na}{EI}$	$+\frac{Na^2}{EI} (1 + \frac{3a}{L})$	$-M \cdot \frac{a}{L}$
$-\frac{PL}{2}$	$-PL$		$+\frac{PL^2}{2EI}$	$+\frac{PL^3}{3EI}$	$-\frac{PL}{2}$
$-Pa (1 - \frac{a}{2L})$	$-Pa$		$+\frac{Pa^2}{2EI}$	$+\frac{Pa^3}{3EI} (1 + \frac{3a}{L})$	$-\frac{Pa^2}{2L}$
$-\frac{WL}{3}$	$-\frac{WL}{2}$		$+\frac{WL^2}{6EI}$	$+\frac{WL^3}{8EI}$	$-\frac{WL}{6}$
$-\frac{Wa}{3} (1 - \frac{a}{2L})$	$-\frac{Wa}{2}$		$+\frac{Wa^2}{6EI}$	$+\frac{Wa^3}{8EI} (1 + \frac{3a}{L})$	$-\frac{Wa^2}{6L}$
$-\frac{WL}{4}$	$-\frac{WL}{3}$		$+\frac{WL^2}{12EI}$	$+\frac{WL^3}{15EI}$	$-\frac{WL}{12}$
$-\frac{Wa}{3} (1 - \frac{a}{2L})$	$-\frac{Wa}{3}$		$+\frac{Wa^2}{12EI}$	$+\frac{Wa^3}{15EI} (1 + \frac{3a}{L})$	$-\frac{Wa^2}{12L}$
$-\frac{5}{12} WL$	$-\frac{2WL}{3}$		$+\frac{WL^2}{24EI}$	$-\frac{11}{60} \frac{WL^3}{EI}$	$-\frac{WL}{4}$
$-\frac{2Wa}{3} (1 - \frac{3a}{2L})$	$-\frac{2Wa}{3}$		$+\frac{Wa^2}{24EI}$	$+\frac{11Wa^3}{60EI} (1 + \frac{3a}{L})$	$-\frac{Wa^2}{4L}$

cases can be found from Table I. If the column is hinged at the bottom the moment at the top is M_A° .

In addition to the fixed-end moments caused by the direct horizontal loads on the column, there is a sway moment M_s caused by all the horizontal forces ΣP acting at, or above, the top. At each end of a column with both ends fixed, $M_s = -\frac{L}{2} \times \Sigma P$; at the top, with a hinged bottom, $M_s = -L \times \Sigma P$.

For asymmetrical loading the restraint moments have the same sign for both halves of the frame.

(2) FRAMES WITH INCLINED COLUMNS.—The stiffness of a beam is, as previously, $K_b = \frac{6EI_b}{L_b}$. The stiffnesses of a column fixed at both ends are:

$$\text{At top, } K_A = \frac{3EI_c}{L_c} \times \frac{m^2}{1 + m + m^2}$$

$$\text{At bottom, } K_f = \frac{3EI_c}{L_c} \times \frac{1}{1 + m + m^2}$$

in which m is the ratio of the distance between the tops of the columns to the distance between the bottoms. For columns hinged at one end, as before $K_A = K_f = 0$.

The carry-over factors for columns with both ends fixed are: From top to

bottom, $C_{bf} = -\frac{1}{m}$. From bottom to top, $C_{fb} = -m$. There is no carry-over factor for beams or for columns with one end hinged.

Moments due to Sway.

TOP STORY.—Considering the top story (Fig. 1) and assuming that the bottom of the column A_1 is hinged, the shearing force S_1 at the bottom is found by balancing the moments of all the forces acting on the top part of the frame about O.

$$S_1 \times (L_0 + L_1) + P_1 \times L_0 \times \sin \alpha + N_1 \times L_0 \times \cos \alpha = 0. \quad (1)$$

from which $S_1 = -(P_1 \times \sin \alpha + N_1 \times \cos \alpha) \times m_1$.

The sway moment for the column, if it is hinged at the bottom, would be

$$M_1^0 = S_1 \times L_1 \quad (2)$$

but if both ends are fixed, and the stiffnesses and carry-over factors are known, it can be shown that the sway moment at the top is

$$M_h = M^0 \times \frac{2 + m}{2(1 + m + m^2)} \quad (3)$$

and at the bottom

$$M_f = M^0 \times \frac{1 + 2m}{2(1 + m + m^2)} \quad (4)$$

Allowance should be made for any asymmetrical load on beam A_1B_1 in equation (1) to obtain the total shearing force.



$$\sin \alpha = \frac{h_0}{L_0} = \frac{h_1}{L_1}$$

$$\cos \alpha = \frac{b_1}{2L_0}$$

$$m_1 = \frac{b_1}{b_2} = \frac{L_0}{L_0 + L_1} = \frac{h_0}{h_0 + h_1}$$

$$m_2 = \frac{b_2}{b_3} = \frac{L_0 + L_1}{L_0 + L_1 + L_2}$$

$$m_1 \times m_2 = \frac{L_0}{L_0 + L_1 + L_2}$$

Fig. 1.

LOWER STORIES.—As for the top story, the frame is assumed to be cut at A_3 and the moments of all the forces on this part are balanced about O.

$$S_2 \times (L_0 + L_1 + L_2) + P_1 \times L_0 \times \sin \alpha + N_1 \times L_0 \times \cos \alpha \\ + P_2 \times (L_0 + L_1) \sin \alpha + N_2 \times (L_0 + L_1) \times \cos \alpha = 0$$

from which $S_2 = S_1 \times m_2 - (P_2 \times \sin \alpha + N_2 \times \cos \alpha) \times m_2$. For the next story below, $S_3 = S_2 \times m_3 - (P_3 \times \sin \alpha + N_3 \times \cos \alpha) \times m_3$. The fixed-end moments due to sway are obtained from formulæ (2), (3), and (4).

Fixed-end Moments due to a Transverse Load on a Column.

The fixed-end moments can be computed by finding the angular deformation at the bottom of the column under load, assuming that the column forms part of a simply-supported beam with one support at the bottom of the column and the other at the point of intersection O (the part from the head to O is considered to be infinitely stiff). The calculation is lengthy and the resulting formulæ are complicated, but an asymmetrical load does not often occur except at joints.

For a uniformly-distributed load W (on the full length) the fixed-end moment for a column hinged at the foot is $M_A^0 = -\frac{WL}{2} \times m$.

For a column with both ends fixed, the fixed-end moments are:

$$\text{At bottom, } M_f = -\frac{WL}{8} \times \frac{1 + 3m + 4m^2}{1 + m + m^2}.$$

$$\text{At top, } M_h = -\frac{WL}{8} \times \frac{3m + m^3}{1 + m + m^2}.$$

If a force P acts at right-angles to a column at a distance aL from the bottom, the fixed-end moments are:

For a column hinged at the foot, $M_A^0 = -PaL \times m$. For a column with both ends fixed:

$$\text{At the bottom, } M_f = -PaL \times \frac{(2 - 3a + a^2) + (2 - a^2)m + 2m^2}{2(1 + m + m^2)}.$$

$$\text{At the top, } M_h = M^0 - M_f \times m,$$

which is the general formula for the moment at the top of a column if the moment at the bottom is known.

For a concentrated load (force or moment) it is sometimes more convenient to introduce an imaginary beam of zero stiffness at the point of application of the load instead of trying to derive complicated formulæ, and to calculate the shearing force and moments and proceed with further calculations as for an actual beam.

Practical Application.

The example which follows explains the procedure and shows the calculations.

When there are several frames of which the top portions are identical and which differ only in height, for example bridge piers or trestles for an inclined conveyor, the work can be reduced by numbering the stories from top to bottom and making the calculations in the same order so that the calculations for the bottom part only of each frame will be different. This method can also be used

to analyse frames in which some columns are vertical and others inclined, but care must be taken to use the correct value of the shearing force where change of inclination occurs. This also applies when the top story forms a gable. All the formulæ in this article apply to prismatic members only.

A coefficient can be applied to the stiffness of the beam to allow for the effect of haunching. An abrupt change of the cross section of a column can be dealt with assuming that an imaginary beam of zero stiffness exists at the point of change. For gradual changes of section it is difficult to derive suitable formulæ; the designer must decide for himself the simplifying assumptions that can be made.


Example.

The dimensions and arrangement of loads are shown in Fig. 2. All members have the same section, and it is assumed that $EI = 1$;

$$\sin \alpha = \frac{12}{12.5} = 0.96; \quad \cos \alpha = \frac{3.5}{12.5} = 0.28.$$

The stiffnesses of the beam = $K_b = \frac{6EI_b}{b}$; therefore $K_1 = \frac{6 \times 1}{6} = 1$,

$$K_2 = \frac{6 \times 1}{13} = 0.46, \text{ and } K_3 = \frac{6 \times 1}{20} = 0.3.$$



$$C_{12} = -2.17$$

$$m_1 = \frac{6'}{13'} = 0.46$$

$$C_{21} = -0.46$$

$$C_{23} = -1.54$$

$$m_2 = \frac{13'}{20'} = 0.65$$

$$C_{32} = -0.65$$

$$C_{34} = -1.35$$

$$m_3 = \frac{20'}{27'} = 0.74$$

Fig. 2.

The stiffnesses of the columns are $K_A = \frac{3EI_c}{L_c} \times \frac{m^2}{1+m+m^2}$

$$\text{and } K_f = \frac{3EI_c}{L_c} \times \frac{1}{1+m+m^2}.$$

First story from the top:

$$K_{12} = \frac{3 \times 1}{12.5} \times \frac{0.46^2}{1 + 0.46 + 0.46^2} = 0.24 \times \frac{0.212}{1.672} = 0.030. \quad K_{21} = \frac{0.24}{1.672} = 0.144.$$

Second story from the top:

$$K_{23} = 0.24 \times \frac{0.65^2}{1 + 0.65 + 0.65^2} = 0.24 \times \frac{0.422}{2.072} = 0.049. \quad K_{32} = \frac{0.24}{2.072} = 0.116.$$

Third story from the top:

$$K_{34} = 0.24 \times \frac{0.74^2}{1 + 0.74 + 0.74^2} = 0.24 \times \frac{0.548}{2.288} = 0.058.$$

FIXED-END MOMENTS.—

First story from the top. Shearing force $S_1 = -(P_1 \sin \alpha + N_1 \cos \alpha) \times m_1$.

$$S_1 = -(11 \times 0.96 - 5 \times 0.28) \times 0.46 = -(10.56 - 1.40) \times 0.46 = -4.22 \text{ tons.}$$

$$M_{12}^0 = S_1 \times L_1 = -4.22 \times 12.5 = -52.8 \text{ ft.-tons.}$$

$$M_{12} = M_{12}^0 \times \frac{2+m}{2(1+m+m^2)} = -52.8 \times \frac{2.46}{2 \times 1.672} = -38.8 \text{ ft.-tons.}$$

$$M_{21} = M_{12}^0 \times \frac{1+2m}{2(1+m+m^2)} = -52.8 \times \frac{1.92}{2 \times 1.672} = -30.3 \text{ ft.-tons.}$$

Second story from the top. Shearing force

$$S_2 = S_1 \times m_2 - (P_2 \sin \alpha + N_2 \cos \alpha) \times m_2.$$

$$S_2 = -4.22 \times 0.65 - 2.0 \times 0.96 \times 0.65 = -2.75 - 1.25 = -4.00 \text{ tons.}$$

$$M_{23}^0 = S_2 \times L_2 = -4.00 \times 12.5 = -50 \text{ ft.-tons.}$$

$$M_{23} = -50 \times \frac{2.65}{2 \times 2.072} = -32.0 \text{ ft.-tons.}$$

$$M_{32} = -50.0 \times \frac{2.30}{2 \times 2.072} = -27.8 \text{ ft.-tons.}$$

Third story from the top. Shearing force

$$S_3 = S_2 \times m_3 - (P_3 \sin \alpha + N_3 \cos \alpha) \times m_3.$$

$$S_3 = -4.00 \times 0.74 - 2.0 \times 0.96 \times 0.74 = -2.96 - 1.42 = -4.38 \text{ tons.}$$

$$M_{34}^0 = -4.38 \times 12.5 = -54.8 \text{ ft.-tons.}$$

$$M_{34} = -54.8 \times \frac{2.74}{2 \times 2.288} = -32.8 \text{ ft.-tons.}$$

$$M_{43} = -54.8 \times \frac{2.48}{2 \times 2.288} = -29.7 \text{ ft.-tons.}$$

TABLE II.

MOMENT DISTRIBUTION TABLE										
JOINT	A ₄		A ₃			A ₂			A ₁	
MEMBER	A ₄ A ₃	A ₃ A ₄	A ₃ B ₃	A ₃ A ₂	A ₂ A ₃	A ₂ B ₂	A ₂ A ₁	A ₁ A ₂	A ₁ B ₁	
STIFFNESS	-	0.0575	0.30	0.1158	0.0480	0.46	0.1434	0.03	1.00	
DISTR. FACTOR	-	0.128	0.631	0.246	0.075	0.706	0.219	0.03	0.97	
CARRY-OVER FMT	-	-1.35	-	-0.65	-1.54	-	-0.46	-2.17	-	
FIXED-END MOM.	-29.87	-32.78	-	-27.75	-31.97	-	-30.32	-58.82	-	
1ST. DIST.	-	+7.45	+38.18	+14.90	+4.67	+43.08	+13.64	+1.18	+37.66	
C.O.	-10.08	-	-	-7.18	-9.69	-	-3.51	-6.31	-	
2ND DIST.	-	+0.88	+4.53	+1.77	+0.92	+8.61	+2.67	+0.19	+6.12	
C.O.	-1.19	-	-	-1.42	-1.15	-	-0.41	-1.23	-	
3RD DIST.	-	+0.17	+0.90	+0.35	+0.12	+1.10	+0.34	+0.04	+1.19	
C.O.	-0.23	-	-	-0.18	-0.23	-	-0.08	-0.16	-	
4TH DIST.	-	+0.02	+0.12	+0.04	+0.02	+0.22	+0.07	-	+0.16	
TOTAL	-41.15	-24.26	+43.73	-19.47	-37.31	+53.91	-16.60	-45.13	+45.13	
SHEAR TABLE										
L	12.5	12.5	20.0	12.5	12.5	13.0	12.5	12.5	6.0	
M/L	-3.29	-1.94	+2.19	-1.56	-2.99	+4.14	-1.33	-3.61	+7.52	
SHEAR	+5.23	-5.23	-4.37	+4.55	-4.55	-8.30	+4.94	-4.94	-15.04	

TABLE III.

FORCES NORMAL TO COLUMN					FORCES PARALLEL TO COLUMN				
	A ₄	A ₃	A ₂	A ₁		A ₄	A ₃	A ₂	A ₁
Ex.V + Ncosα	-	-	-	-1.40	Ex.V + Nsina	-	-	-	-4.80
Ex.H + Psina	-	+1.92	+1.92	+10.36	Ex.H - Pcosα	-	-0.56	-0.56	-3.08
Upper col.	+5.23	+4.58	+4.94	-	Upper col.	-35.61	-30.85	-22.32	-
Beam + S ₆ cosα	-	-1.22	-2.32	-4.21	Beam + S ₆ sina	-	-4.80	-7.97	-14.44
Lower col.	-	-5.23	-4.55	-4.94	Lower col.	-	+35.61	+30.85	+22.32
Total	+5.23	+0.02	+0.01	+0.01	Total	-35.61	0	0	0

The moment distribution is shown in Table II, which also gives the shearing forces. The balance of the joints is checked in Table III.

The loads on the foundation are,

Horizontal :

$$H_A = + 35.61 \times 0.28 + 5.23 \times 0.96 = + 9.97 + 5.02 = + 14.99 \text{ tons.}$$

Vertical :

$$V_A = - 35.61 \times 0.96 + 5.23 \times 0.28 = - 34.19 + 1.46 = - 32.73 \text{ tons.}$$

Bridge Engineering in Britain.

THE Minister of Transport stated in the House of Commons on February 3, 1960: "My visit to the continent satisfied me that British design (of bridges) and construction match work being done elsewhere. It may not therefore be necessary to make radical changes in present arrangements but, to ensure that full

advantage is taken of the latest ideas and techniques, I am continuing to study whether it is desirable to try out new arrangements experimentally. I intend in any case that the partnership between my Ministry, bridge designers, and bridge builders should be made as close as possible."

Book Reviews.

"Dock and Harbour Engineering." Vol. 2. The Design of Harbours. By H. F. Cornick. (London: Charles Griffin & Co., Ltd. 1959. Price £6 6s.)

This book is the second volume of a work comprising four volumes which will replace the well-known books entitled "Dock Engineering" and "Harbour Engineering" by the late Brynson Cunningham. The new work retains what is of permanent value in the original books, which were first published more than fifty years ago, and includes much new matter in the collation of which the author has drawn on his own experience of harbour works, and has supplemented this by examples taken from the literature of the subject; knowledge of what has been done successfully or otherwise is of more value than theory when dealing with the forces of nature.

A brief history of harbours is followed by a description of the principles and factors affecting the design of harbours, breakwaters, pier-heads, jetties, and landing stages. Hydrographic surveying and the formation and maintenance of channels are included. There is a useful section on tides and waves, and much information is given on the forces exerted by waves and the distribution on walls of the pressures due to this cause. The section on piling is based on formulae and data published elsewhere. A useful feature is the consideration of the impact of vessels on piled jetties, and details are given of many types of fenders. The construction of harbour works is intended to be the subject of a subsequent volume.

"Principles of Pavement Design." By E. J. Yoder. (London: Chapman & Hall, Ltd. 1959. Price 106s.)

This book of over five hundred pages, the text of which is based on the author's lectures, deals primarily with methods of the design of flexible and rigid roads and airfield runways used in the U.S.A. Construction is excluded except in so far as the procedure affects design. There appears to be a leaning towards computational design, based on more or less exact appraisal of the properties of the soil, magnitude of the loading, quality of the materials forming the road, and similar data, whereas elsewhere the tendency appears to be for experience to supplement calculations. A knowledge of soils

mechanics and the making of concrete is assumed.

The question of whether or not to provide expansion joints in concrete roads is dealt with by tabulating the practice in the various states, from which it appears that in the majority of cases joints are no longer provided except in special positions, such as at bridges. If joints are provided in roads, the spacing is within the wide limits of 61 ft. and 1200 ft. Transverse contraction joints are commonly provided and the spacing is generally from 15 ft. to 40 ft., although in some cases the spacing is 100 ft. The effect of climatic conditions is noticeable in so far that the factors taken into account in design have different degrees of importance in districts where the weather is continually warm compared with localities where cold winters alternate with hot summers. There is a good chapter on defects which is comprehensive in its dealing with troubles encountered with flexible roads. There does not appear to be any direct comparison of rigid concrete and flexible roads as regards their relative first costs and maintenance charges.

"Berechnungsgrundlagen für Bauten."

Compiled by E. L. Wedler. 23rd edition. (Berlin: Wilhelm Ernst & Sohn. 1959. Price 17 D.M.)

In this edition German codes of practice relating to the design of buildings are given in full, with explanatory notes. Codes are now included for foundations, materials, rendering, timber construction, steel, combined concrete slab and steel girder construction, light-alloy structures, vibration of foundations carrying heavy machinery, and foundations in regions subject to earthquakes. It is proposed to give codes for concrete construction in a later volume.

"Planning." By S. Rowland Pierce, Patrick Cutbush, and Anthony Williams. (London: Iliffe & Sons, Ltd. Price 63s.)

COMPRISES 530 pages of notes on the planning of buildings for nearly all purposes, with more than 600 drawings.

"Staircase Manual." By J. A. Corns. (London: Cleaver-Hume Press, Ltd. Price 30s.)

A book for carpenters with working drawings and descriptive notes on the construction of plain and ornamental, straight and curved, wooden staircases and handrails.

Exposed-aggregate Slabs in the South of England.

MR. T. B. SMITH, A.M.I.C.E., has contributed the descriptions in the following of some recent examples of precast slabs with exposed-aggregate surfaces which have been used on the façades of buildings in the south of England.

Some types of surfaces obtainable with exposed aggregate are shown in *Fig. 1*. The aggregates vary in size from fine sand to 6-in. flints. In selecting the most suitable size of aggregate it is important to consider the total area of the wall and the distance from which it will be viewed. The greater the distance from which the wall is normally viewed the larger should be the aggregate if the texture is to be effective. A contrast between the colours of the aggregate and the background, or

the use of aggregate of two or more colours, is advisable if the wall will be seen at a distance. The aspect of the building and the shape and degree of exposure of the aggregate should be considered.

Fig. 2 is an example of the use of large aggregate, which in this case are 3-in. to 4-in. grey flints which have been rounded by use in the washmills of a cement works. The stones are set in a background of concrete with smaller aggregate of slightly lighter colour; the slabs have a plain margin of ordinary Portland-cement mortar. The slabs were cast face downwards on a bed of sand.

Broken flints (*Fig. 3*) set in a matrix of white cement mortar were used for the




Fig. 1.—Some Types of Exposed-aggregate Surfaces.




Fig. 2.—Large Flints.

slabs of a wall of a block of residential flats at Dover, for which Messrs. Dalglish & Pullen are the architects. In this case the slabs were cast face upwards and the stones were laid by hand on the backing concrete and then tamped to a level surface. Owing to the lack of experienced flint knappers the stones were broken by hand by unskilled men. The slabs in Fig. 4 were also cast face upwards, the

large aggregate in this case being pieces of grey-gold Cornish slate $\frac{1}{4}$ in. thick. This type of finish is also used for paving slabs.

When deciding the colour for exposed-aggregate slabs it is advisable to select a darker hue than that required for the finished work; large slabs in a wall generally appear lighter in colour than a small sample viewed at close quarters. The



Fig. 3.—Split Flints set in White Cement Mortar.

colour of the backing concrete should be the same as that of the facing mixture, and the texture should be uniform. When using ordinary grey Portland cement care is needed to ensure that the colour is consistent. It may be necessary to obtain at one time sufficient cement to make all the slabs for one wall, or to blend the cement to obtain an even colour. Precautions must also be taken with the aggregates. Although some quarries guarantee the gradings of their materials, it may be necessary to screen the material before it is used. The colour of the stones from different faces of a quarry may differ, and before commencing to make a large number of exposed-aggregate slabs sufficient aggregate for the entire batch should be obtained, and it may be necessary to blend the materials.

Makers of exposed-aggregate panels generally have on display standard samples from which a customer can select one suitable for his purpose. It is generally possible to make other specimens with other textures and colours if none of the standard slabs is acceptable. It is important that a sample having an area of at least 4 sq. ft. should be examined before a decision is made. It is also necessary to realise that the surfaces of slabs made in large numbers are not likely to be as uniform as that of one slab made for the purpose of a specimen. Slight variations may, however, be desirable from the point of view of appearance. An example of a wall where the appearance




Fig. 5.—An Elevation of Dartford College.

is improved by a slight variation in colour is Strand School, Tulse Hill, London (Fig. 6), designed by the Architect's Department of the London County Council. In this example the natural appearance of green slate is simulated by using green aggregate in very small pieces.

The combination of exposed-aggregate and moulded patterns is shown in Fig. 5; in this case blocks of cast stone 6 in.




Fig. 4.—Slate.



Fig. 6.—Lift Enclosure at a School.



Fig. 7.—Balustrades at Residential Building in West London.

square are combined with exposed flint aggregate. This illustration is of Dartford Technical College, which was designed by Mr. S. H. Loweth, then County Architect for Kent. Similar panels are used on shops at the new town of Hemel Hempstead.

Slabs of completely contrasting colours and texture are frequently used for decorative effect by using different aggregates. In the example in *Fig. 9*, which illustrates the end wall of an office building in East London (Messrs. L. K. Watson & H. J.




Fig. 8.—Residential Building in West London.

F—April, 1960.




Fig. 9.—Office Building in London.

Coates, architects), the colours of the aggregates are light green and very dark blue.

An example of covering the entire structural frame and walls of a building with exposed-aggregate slabs is shown in *Fig. 8*, which illustrates the new Hall of Residence for London University, the architects for which are Messrs. Richard Sheppard, Robson & Partners. On the side walls story-height slabs are provided between the beams at each floor-level. The beams in the side walls and the beams and columns on the front elevation are covered with precast slabs, as are also, in slabs of contrasting colour, the balcony beams. The surface of the slabs has the appearance of finely-axed light-grey granite. The upper part of the balcony beams comprises translucent quartz and white-cement concrete. The joints between the precast slabs are shown in *Fig. 10*, and *Fig. 7* illustrates the balustrade at ground-level which has the same light-grey exposed granite finish as the members at higher levels.

The shape of the aggregate affects the tone of the slabs after weathering. Rounded aggregates are largely self-cleaning. Angular aggregates of rough texture tend to collect dirt, but this is




Fig. 10.—Detail of Residential Building in West London.

generally confined to the cement background; for this reason the area of exposed cement between the pieces of stone should be as small as practicable. It may be advisable for the cement background to be darker than the aggregate if the slabs are to be subjected to considerable atmospheric pollution.

Attempts have been made in Great Britain to improve the appearance and weathering qualities of exposed-aggregate slabs by the application of clear glazes, lacquers, and silicone washes. Some of these treatments tend to decrease the contrast in colour of the aggregates and backing, but it is not yet known how long these treatments are likely to be effective.

The aggregate, known as "Mineralite",

used for the slabs in Figs. 6 and 9, is a finely crushed aggregate generally of varied and brilliant colours. It is of Scandinavian origin and has been used for about thirty years on the Continent and for about seven years in Britain. It is supplied as a dry mixture of aggregate and cement. The final surface treatment in making slabs with this aggregate is to pat the face with a felt pad. It is claimed that the colours of the granites and other materials composing this aggregate cannot fade and that the surface does not craze.

The slabs described in the foregoing were made by Kendell's Stone & Paving Co., Ltd., with the exception of those in Fig. 5 which were made by the Atlas Stone Co., Ltd.

Research in Portugal.

THE following papers have been issued by the Portuguese Laboratório Nacional de Engenharia Civil, Lisbon. No prices are stated. The first three are printed in the English language and the others are printed in the Portuguese language with short summaries in English.

"The Design of Reinforced Concrete Beams", by J. Ferry Borges and J. Arga E. Lima.

"Rectangular Staircases without Beams", by J. Ferry Borges.

"Portuguese Experience on the Com-

paction Control of Earth Dams", by Manuel Rocha, Armando Palma Carlos, José Folque, Virgílio Penalva Esteves.

"A Determinação de Coeficiente de Poisson do Betão das Nossas Barragens a Partir das Extensões Medidas In Situ", by M. Q. Guerreiro.

"O Panorama Hidroeléctrico no Quadro do Desenvolvimento Industrial Brasileiro", by J. Laginha Serafim.

"O Comportamento Térmico das Barragens de Betão", by António Ferreira da Silveira.

Precast Construction of a Factory.

THE main building at a new factory for Messrs. Meggeson & Co., Ltd., at Camberwell, London, is about 195 ft. long and 165 ft. wide. There is also a canteen building of about 75 ft. by 30 ft. The structures are partly of two stories (Fig. 4). The first floor is designed for an imposed load of 200 lb. per square foot. To save time of construction as much of the work as possible was precast.

The primary beams are splayed in plan




Fig. 1.—Connection of Internal Columns and Beams.

at the supports in order to provide sufficient resistance to compression without having to provide vertical haunches, which would decrease the clearance below the beams, and without having to provide reinforcement in compression. The columns are at 20 ft. centres in both directions and secondary beams are provided so that the floor slabs span about 10 ft.

The floor slabs are 6 in. thick and comprise 3 in. of concrete on 3-in. precast slabs reinforced with expanded metal. The upper slabs were cast in alternate



Fig. 2.—Precast Beams: showing Slots for Connections.

panels to reduce the effects of shrinking. Since the frame is composed entirely of precast members, little shrinking of the structure as a whole is expected.

The external columns were precast in one piece for the full height of the two stories. The internal columns are also precast and extend to the first floor only. Connecting the columns and secondary beams is a steel plate embedded in the column and inserted in a slot in the beam (Fig. 1). Inverted U-bars projecting from the top of the precast beams above the slots (Fig. 2) bear on the top edge of the plate. Deformed bars are welded to the top and bottom of the plates, through which holes are drilled to provide a bond when the joint is concreted. The slabs





Fig. 3.—Main Beam on Column: showing Haunch and Connecting Plate.



adjacent to the external beams were cast in place, and are reinforced in the top and bottom to prevent the beams twisting.

The primary beams are supported on steps in the external columns (*Fig. 3*), and on the tops of the internal columns. Reinforcement projects from the external columns into the part of the primary beams which was cast in place with the floor slab. The connections between the primary and secondary beams are also by means of steel plates which are embedded

in the primary beams (*Fig. 3*). The secondary beams are designed as being freely supported, but since liquid sugar used in the factory might be spilt on the floor, the secondary beams were made fully continuous to prevent cracking at the joints.

The architects are Messrs. Ronald Ward & Partners. The consulting engineers are Messrs. Hajnal & Myers, and the contractors were Messrs. H. Fairweather & Co., Ltd.

Widening of Bridge of Don, Aberdeen.

THE existing masonry bridge over the River Don at Aberdeen was built between the years 1827 and 1830 to the design of Thomas Telford. Excluding the approaches, the structure is 520 ft. long and has five segmental arches each of 75 ft. clear opening. The arches, spandrel walls, and the slabs carrying the roadway are of granite. The width of the bridge between the parapets was 24 ft., and has been increased to 66 ft. The new work, which was completed in 1959, is separated from the old in order to prevent additional load being carried on the old foundations. Bored piles were used under the new piers to avoid vibration, which might damage the old foundations which had settled. The granite slabs under the original road and footpath were taken up and replaced by reinforced concrete slabs, thereby

reducing the load on the old piers by about 1000 tons.

The new superstructure has reinforced concrete vault slabs, transverse walls, and deck slabs. The piers, voussoirs, and spandrel walls are faced with granite (*Fig. 1*), dressed to match the old bridge. The old parapets were taken down, the stones cleaned, and the parapets rebuilt, one in its original position and the other on the new structure.

The total cost, including roadworks, was about £282,000, of which £98,000 is the cost of the masonry. The engineer was Mr. A. G. Booth, City Engineer of Aberdeen, and the consulting engineers were Considère Constructions, Ltd. The main contractors for the work of reconstruction were Messrs. H. M. Murray & Co., Ltd.




Fig. 1.

Concrete at Bradwell Nuclear Power Station.

THE 300-megawatt nuclear power station being erected at Bradwell, Essex, for the Central Electricity Generating Board by the Nuclear Power Plant Co., Ltd., contains 200,000 cu. yd. of concrete which will be placed in the course of three years but most of which has been placed in a period of two years. There are many different types of concrete. The concrete used for structural purposes is classified as concrete of ordinary quality and special concrete of guaranteed density for shield-walls and the like. The most satisfactory mixtures using the aggregates available are determined in the contractors' main laboratory, but routine adjustments and testing are done at a laboratory on the site.

Ordinary Structural Concrete.

Particulars of the three principal mixtures of ordinary structural concrete are

at 28 days is 4700 lb. per square inch with a standard deviation of 445 lb. per square inch and a coefficient of variation of 9.1 per cent.

Other concrete for the shielding construction has a minimum dry density of 165 lb. per cubic foot for which a mixed aggregate comprising gravel and barytes is used. The aggregate for concrete having a density of 200 lb. per cubic foot is entirely barytes. There is also a small quantity of special concrete having a minimum density of 340 lb. per cubic foot in which iron shot is used as aggregate. The densities of cubes of concrete for shielding were determined after drying to constant weight in an oven at 105 deg. C. The density of 9-in. diameter cores cut out of concrete in the work was the same (about 144 lb. per cubic foot) as that of the cubes.

The contractors for the civil engineering

TABLE I.—ORDINARY STRUCTURAL CONCRETE.

Proportions		Maximum size of aggregate (in.)	Minimum specified crushing strength (lb. per sq. in.)	Crushing strength (lb. per sq. in.)	Standard deviation (lb. per sq. in.)	Coefficient of variation (per cent.)
Volumetric	By weight					
1:2:4	1:2.25:4.5	1½	3300	4500	440	9.8
1:2:4	1:2.15:3.6	1½	3300	4750	435	9.2
1:1½:3	1:1.8:3.2	1½	4125	5500	410	7.5

given in Table I and include the nominal volumetric proportions and the actual proportions by weight. The crushing strengths are the average strengths at 28 days of all cubes of each mixture. The standard deviations and coefficients of variation are given for each mixture. The aggregates are gravel and sand obtained from local pits. The slump is generally 2 in.

Concrete for Shield-Walls.

The concrete for walls of the reactors and elsewhere, where a shield against nuclear radiations is required, has a dry density of not less than 140 lb. per cubic foot and a compacting factor of 0.87. The aggregate is gravel brought by sea in barges from Brightlingsea because local aggregates are not sufficiently consistent in weight. The mixture is 1:2.5:6.1 by weight and the average crushing strength

and building works are Sir Robert McAlpine & Sons, Ltd.

The Late Mr. Maxwell Ayrton.

THE death of Mr. Maxwell Ayrton, the architect, occurred in February at the age of 85 years. Mr. Ayrton was well known as an exponent of architectural concrete and contributed to this journal on that subject. The most notable of his earlier works, jointly with Mr. Simpson, was the British Empire Exhibition and Stadium at Wembley. Among other major reinforced concrete structures for which he was the architect are the bridge over the Thames at Twickenham and the Lea Valley viaduct. During the past decade he was in partnership with Mr. Courtenay Theobald.



Fig. 1.

A New Bridge over the Mersey near Manchester.

KINGSWAY bridge (Fig. 1) carries the Cheadle by-pass road over the River Mersey which, at the site of the bridge, is about 110 ft. wide. Provision is made for the sudden and considerable floods, to which the river is liable, by spans of 51 ft. 6 in. on each side of the main span which is 104 ft. long. The bridge, which is designed for Ministry of Transport standard loading and abnormal loading, carries two carriageways each 24 ft. wide, a central reservation 4 ft. wide, two 7-ft. footpaths and a verge 12 ft. wide adjoining each footpath, which enables the carriageways to be widened in the future to 36 ft. The overall width is 91 ft. 6 in. The angle of skew is 30 deg.

The bridge is a reinforced concrete structure, the two side spans of which cantilever about 24 ft. 6 in. over the river and support a suspended span of 55 ft.

(Fig. 3). The piers are founded on good sandstone, which occurs at about 1 ft. below normal water level on the north side of the bridge and 6 ft. below normal water level on the south side. Excavation and construction of the foundations were carried out in cofferdams.

The girders, which are 2 ft. wide and vary in depth from 8 ft. at the piers to 5 ft. at the supports of the suspended span, were cast in place up to the level of the underside of the deck slab. Transverse beams are provided to ensure good distribution of the imposed load. The 10-in. deck slab was cast subsequently. There are no transverse beams under the central reservation and there is a gap 1 in. wide in the deck along the entire centre-line of the bridge.

The beams forming the suspended span are 4 ft. deep at the middle of their span, and were precast on an approach road and rolled on bogies along a temporary Bailey bridge erected between the cantilevers. The beams were lifted from the Bailey bridge by two mobile cranes (Fig. 2) and lowered into position. The Bailey bridge was moved for each pair of beams to reduce the distance the beams had to be lifted. The cantilevered girders are supported on the piers by mild-steel roller bearings in galvanised steel grease-boxes. The suspended girders are supported on rocker bearings at the north end and on roller bearings at the south end. A roller bearing at one end of the suspended span and a transverse joint through the deck and the road surface enable the deck to move due to changes of temperature. Mild-steel plates are embedded in the concrete on both sides of the joint which is covered by a phosphor-bronze plate




Fig. 2.—Erecting Precast Beams.

April, 1960.






Fig. 3.—Section and Details of Bridge over



SECTION



Bridge over the Mersey, near Manchester.

1 in. thick secured to the mild-steel plates by $\frac{1}{2}$ -in. setscrews.

The wing walls are set in slots in the abutments, of which they are structurally independent. The spaces between the abutments and wing walls are filled and are sealed with a rubber-bitumen compound. The copings and pilasters of the wing walls are of Portland stone.

Wrought timber shutters were used for most of the work. The shutters for the faces of the exterior girders and the soffit of all the girders and beams were faced with plywood. The concrete for the piers, abutments, wing walls, girders, beams and deck had water-cement ratios of up to 0.55 and crushing strengths at 28 days of at least 3300 lb. per square inch. The aggregates are North Staffordshire sand and gravel up to $\frac{1}{2}$ in. in size. The con-


crete for the piers, abutments and wing walls and northern cantilever was mixed on site. Ready-mixed concrete was provided for the southern cantilever and the suspended span. The bridge was constructed in twenty months.

The Manchester City Surveyor, Mr. R. Nicholas, C.B.E., controlled the work for the Manchester Corporation and the Cheshire County Council. The consulting engineers for the bridge and its approaches were Messrs. L. G. Mouchel & Partners. The Manchester City Architect, Mr. L. C. Howitt, F.R.I.B.A., advised on the elevation of the bridge, the aesthetic design of which was approved by the Royal Fine Arts Commission. The main contractors were Tarmac, Civil Engineering, Ltd. The ready-mixed concrete was supplied by Trumix Concrete Ltd.

FIFTY YEARS AGO.

From "CONCRETE AND CONSTRUCTIONAL ENGINEERING", April, 1910.

Barrel Vault Roofs.



"Reinforced concrete construction is gaining favour with architects for the construction of church roofs, the principal advantages being the practicability of constructing large barrel and domical roofs without unsightly trusses, tie rods, etc., and the low cost of upkeep. An example of this form, and one of the first to be constructed throughout of reinforced concrete, is that of St. Aloysius Roman Catholic Church, Glasgow. The roofs over the nave, transepts, and apse are in the form of semicircular arches, the nave roof having a clear span of 44 ft. 6 in., and a length of 65 ft. The nave roof is supported on arch ribs, reinforced in such a manner as to take the whole of the stress due to thrust without putting any thrust on the side walls, where the load is vertical; the ribs carry a $4\frac{1}{2}$ -in. slab forming the roof covering."

Nomograms for the Design of Beams and Slabs by the Load-factor Method.—III.*

By J. C. STEEDMAN.

Rectangular Beams and Solid Slabs with Reinforcement in Tension only.

NOMOGRAMS NOS. 1C and 2C on pages 170 and 171 are supplementary to the nomograms given in this journal for February 1960, and apply to the design of rectangular beams and solid slabs respectively provided with reinforcement in tension only and if the permissible stress in the concrete is 1500 lb. per square inch.

Flanged Beams with Reinforcement in Tension and Compression.

Nomograms Nos. 6 and 7 (pages 172 and 173) aid the calculation of the area of the compression flanges of tee-, ell-, and I-beams and the area of reinforcement needed. The nomograms give results slightly more accurate than the Code, as the lever arm is measured to the centre of the area of the stressed concrete and not to the centre of the slab; it is therefore unnecessary for the designer to estimate the accuracy of the solution when the area of the rib is large in relation to the area of the flange as may be the case in hollow-tile slabs. If preferred the area of the compression flange may be determined from Nomogram No. 6 and the cross-sectional area of reinforcement required calculated from the expression

$$A_{st} = \frac{\text{bending moment}}{\left(d_1 - \frac{d_2}{2}\right)p_{st}} \text{ as in the Code.}$$

The equations on which the nomograms are based are

$$\frac{M}{bd_1^2p_{cb}} = \frac{2}{3} \left[\frac{d_s}{d_1} \left(1 - \frac{d_s}{2d_1} \right) + \frac{b_r}{b} \left(\frac{d_n - d_s}{d_1} \right) \left(1 - \frac{d_n}{2d_1} - \frac{d_s}{2d_1} \right) \right],$$

$$r_{st} = \frac{200p_{cb}}{3p_{st}} \left[\frac{d_s}{d_1} + \frac{b_r}{b} \left(\frac{d_n - d_s}{d_1} \right) \right].$$

When the value of $\frac{d_s}{d_1}$ is greater than the greatest value obtainable from the section (when $\frac{d_n}{d_s}$ is less than 0.5) reinforcement in compression must be provided and Nomogram No. 4A, 4B or 5 (see Part II) applies.


EXAMPLE No. 6.—An ell-beam having a rib 10 in. wide, an effective depth of 18 in., and a flange 30 in. wide and 4 in. thick is subjected to a bending moment of 1,600,000 in.-lb. Determine the cross-sectional area of reinforcement required if $p_{st} = 20,000$ lb. per square inch and $p_{cb} = 1000$ lb. per square inch.

$$\frac{d_s}{d_1} = \frac{4}{18} = 0.222; \quad \frac{b_r}{b} = \frac{10}{30} = 0.333; \quad \frac{M}{bd_1^2p_{cb}} = \frac{1,600,000}{30 \times 18^2 \times 1000} = 0.165.$$


(Continued on page 174.)

* Concluded from March number.


No. 1C.—DESIGN OF RECTANGULAR BEAMS BY THE LOAD-FACTOR METHOD.
Reinforcement in Tension Only.




No. 2c.—DESIGN OF SOLID SLABS BY THE LOAD-FACTOR METHOD.
Reinforcement in Tension Only.



No. 6.—DESIGN OF FLANGED BEAMS BY THE LOAD-FACTOR METHOD.
Position of Neutral Plane.



No. 7.—DESIGN OF FLANGED BEAMS BY THE LOAD-FACTOR METHOD.
Reinforcement in Compression and Tension.



(Continued from page 169.)

From Nomogram No. 6, $\frac{d_n}{d_1} = 0.450$ and, from Nomogram No. 7, $r_{st} \times R = 19.75$.

Therefore $r_{st} = \frac{19.75}{20} = 0.99$ per cent. and $A_{st} = \frac{0.99}{100} \times 30 \times 18 = 5.33$ sq. in.

According to the formula in the Code, $A_{st} = \frac{1,600,000}{16 \times 20,000} = 5$ sq. in.

Cardboard Formers for Ribbed Slabs.

INVERTED cardboard boxes with internal stiffeners (Fig. 1) are being used in the U.S.A. as formers in ribbed slabs. The boxes are impregnated with wax and sealed at the factory with waterproofed tape 3 in. wide; at the construction site the bottoms of the boxes are dipped into hot paraffin (Fig. 1) to provide extra protection from the weather. The boxes are fixed to the shuttering by staples (Fig. 2) and the joints between them are covered with waterproofed tape; about five minutes are required to fix each box. It is claimed that when they are in position the boxes may be walked on in any weather without damage. When concrete has been placed and has hardened the shuttering is removed (Fig. 3) and the boxes can be pulled out by hand and used again. The cost in the U.S.A. of a



Fig. 2.




Fig. 1.




Fig. 3.

box measuring 2 ft. by 2 ft. by 1 ft. 2 in. is 25 cents (about 1s. 9d.). The boxes are supplied by the Container Corporation of America.

New Dams for Hydro-electric Works in Scotland.

SOME of the dams included in the hydro-electric works being installed by the North of Scotland Hydro-electric Board, which have been completed recently, or are in course of construction, or are about to be commenced are described in the following.* The works for the Conon Valley and Breadalbane schemes are nearing completion. Work has started on the Loch Awe scheme and the Strathfarrar and Kilmorack scheme.

Conon Valley Scheme.

Constructional work on the Conon Valley hydro-electric works in Ross-shire,

struction for part of its length of 1670 ft., but the central part 800 ft. long is a concrete gravity structure, founded on rock (Highland schist), and forms the spillway. The greatest height is 100 ft. and the width at the base of the central part is 90 ft. The bridge which carries a road over the spillway is of reinforced concrete and comprises twenty-eight spans each of 26 ft. The total quantity of concrete in the central part including the bridge is 185,000 cu. yd. The Meig dam, which is 540 ft. long and has a maximum height of 64 ft., is in part an earth embankment with a concrete core-




Fig. 1.—Glascarnoch Dam.

which was commenced in 1947 and was completed recently, comprises several dams, twenty miles of tunnels, fifteen miles of aqueducts, six power stations, and extensive ancillary works. The main dams are at Fannich, Vaich, Glascarnoch, Meig, Luichart, and Torr Achilty and in Glen Orrin. There are smaller dams at Loch Droma and Loch a' Chuillinn, and a barrage at Achanalt. The generating station associated with the Fannich dam has been in operation since 1950.

The Vaich dam, which is an embankment of earth and rock with a core-wall of concrete, is 780 ft. long and has a maximum height of 80 ft. The Glascarnoch dam (Fig. 1) is of similar con-

struction, in part a gravity concrete structure, and elsewhere a concrete buttress dam. The Fannich and Loch Droma dams are rock-fill structures with a sealing membrane on the upstream faces.

The Luichart dam, which raises the level of the water in Loch Luichart by 40 ft., is a gravity structure of plain concrete and is 60 ft. high and 720 ft. long; the width at the base is 40 ft. The quantity of concrete is 41,000 cu. yd. The bridge over the spillway, which comprises twenty-eight spans each 26 ft. long, extends the entire length of the dam and has a prestressed concrete deck, utilising the Freyssinet and Lee-McCall systems; this structure is one of the first prestressed concrete structures erected for the North of Scotland Hydro-electric Board. (The central section of the Ailt-na-Lairige dam is also prestressed.* A fish-pass of the Borland type is provided.

The Torr Achilty dam incorporates the power-house and is similar to the

* Many of the dams in earlier schemes, which are now complete, are described in past numbers of this journal as follows. Loch Sloy dam: December 1948 and December 1950. Clunie and Pitlochry dams: January 1949, February 1949, and December 1950. Mullardoch and Rosevean dams (Glen Affric scheme): February 1951. Clunie and Loyne dams (Glen Moriston scheme): August 1954, January 1955, and December 1956. Ailt-na-Lairige dam: July 1956. Loch Quoich dam: December 1956.

dam at Pitlochry on the Tummel-Garry works.* The width at the base is 40 ft. and the total quantity of concrete is 22,000 cu. yd.

The dam at Glen Orrin is 1080 ft. long and has a maximum height of 150 ft. It is a concrete gravity structure incorporating a Borland-type fish-pass.

The barrage at Achanalt is a reinforced concrete structure in which there are four gates each 30 ft. wide, a free spill-way 33 ft. long, and a weir semicircular in plan and 370 ft. long. The quantity of concrete is 1600 cu. yd. A fish-lock is provided between the gates.

The consulting civil engineers for the Conon Valley works are Sir Alexander Gibb & Partners. The contractors are as follows, Vaich, Glascarnoch, and Luichart dams and the Achanalt barrage:

of 40 ft. The greatest width at the base is 30 ft. The quantity of concrete is 21,000 cu. yd. A fish-pass is provided.

The Giorra dam (*Fig. 2*) will raise the level of Loch Giorra by 90 ft. It is a massive-buttress dam 1540 ft. long and has a maximum height of 110 ft. The width at the base is 80 ft. and the quantity of concrete is 91,000 cu. yd.

Lochan-na-Lairige dam in the Lawers section of this project, which was commenced in 1951 and was completed a few years ago, is also a massive-buttress dam 1100 ft. long and has a maximum height of 130 ft. The dam, which is flanked by an earth embankment 300 ft. long, has raised the level of the water in the loch by 90 ft. The length of the spillway weir is 54 ft. 6 in. and is designed to deal with 1280 cu. ft. per second.



Fig. 2.—Giorra Dam.

Messrs. Reed & Mallik, Ltd. Meig and Glen Orrin dams: Messrs. Duncan Logan, (Contractors), Ltd. Torr Achilty dam: Messrs. William Tawse, Ltd.

Breadalbane Scheme.

Construction of the Killin section of the Breadalbane hydro-electric works in West Perthshire is nearing completion and includes three dams.

Luberoch dam, which (*Fig. 4*) raises the water-level in Loch Lyon by 77 ft. to form the main storage reservoir in this project, is a massive-buttress dam 1740 ft. long. The maximum height above the foundations is 130 ft. and the greatest width at the base is 80 ft. The quantity of concrete is 160,000 cu. yd.

Stronuich dam is a solid gravity dam 702 ft. long and has a maximum height

in the St. Fillans section of this scheme, the Lednock dam (*Fig. 3*), which was completed in 1937, is a diamond-head buttress dam 950 ft. long having a maximum height of 129 ft. The greatest width at the base is 120 ft. and the quantity of concrete is 110,000 cu. yd. The length of the spillway is 200 ft.

The consulting civil engineers for the Killin and Lawers works are Messrs. James Williamson & Partners, Ltd. The contractors for the Luberoch dam are Messrs. James Miller & Partners, Ltd. The contractors for the Stronuich and Giorra dams are Messrs. Edmund Nuttall, Sons & Co., (London), Ltd. The contractors for the Lochan-na-Lairige dam were the Cementation Co. Ltd. The consulting engineers for the St. Fillans works were Sir M. MacDonald & Partners, and the contractors for the Lednock dam were Messrs. Taylor Woodrow Construction, Ltd.

* See footnote on page 175.

The £.s.d of OSAL* —Waterproofing Concrete

**It's
not
the cost
per gallon
but
the cost per yard
that counts**

On this basis Tricosal, which waterproofs a cu. yard of 1 : 2 : 4 concrete for only 7/-, is the most economical as well as the most efficient additive. It waterproofs integrally and, being a liquid, mixes with the gauging fluid and is evenly distributed throughout the mix.



Tricosal is now
available in non-
returnable con-
tainers.


For 30 years or more Tricosal has been specified by leading architects not only for waterproofing but for hardening cement and concrete and increasing their resistance to oils and acids. Send for Information Leaflet No. 1.

* OSAL is the generic name for the products of A. A. Byrd & Co. Ltd.—“Florosal” for Surface Hardening and protection of Concrete, Stone and Cement—“Neocosal” for Surface Waterproofing of Bricks, Concrete and Stone, and “Tricosal”. Literature on each individual product is available from

A. A. BYRD & CO. LTD. (Dept. C.I.), 210 Terminal House,
Grosvenor Gardens, London, S.W.1. Phone: SLOane 5236

Grams: Byrdicam, Watphone, London

Works: Basingstoke, Hants.



OVER *
the
Forth

* UNDER
the Clyde

Colvilles Reinforcing Bars are being used extensively in the Forth Road Bridge project and in the approaches and portals of the new Ten million pound Clyde Tunnel. For hot-rolled, indented reinforcing bars specify "COLBOND 60" which have a guaranteed minimum yield point of 60,000 lbs. per square inch.



COLVILLES

FITNESS FOR PURPOSE STEELS

COLVILLES LIMITED 195 West George St., Glasgow C.2.




Fig. 3.—Lednock Dam.

Strathfarrar and Kilmorack Scheme.

The main civil engineering contracts for the hydro-electric works at Strathfarrar and Kilmorack in the counties of Inverness and Ross and Cromarty were awarded early in 1959. The main dam, which will be an arch dam 110 ft. high, will be about a mile downstream from Loch Monar in Strathfarrar.

There will be a subsidiary dam 50 ft. high near by. These dams will raise the level of the water in the loch by 75 ft. Water will then pass through a tunnel $5\frac{1}{2}$ miles long to a power station at the west end of Loch Beannachran. Near the outlet of the loch there will be a small dam by means of which the level of the water in the loch will be raised by 8 ft.

There will also be two dams each about 50 ft. high on the River Beaulay, one near the Crask of Aigas and the other at Kilmorack; these dams are combined with the power stations. The entire works including power stations, tunnels, dams,

aqueducts, and ancillary works will take about five years to construct. The estimated cost is £14,250,000. Fish-passes operating on much the same principle as a canal lock will be installed at the Beannachran, Aigas, and Kilmorack dams.

The consulting civil engineers for the Strathfarrar and Kilmorack schemes are Sir William Halcrow & Partners. The Mitchell Construction Co., Ltd., are the contractors for the two dams at Loch Monar. Messrs. Duncan Logan (Contractors), Ltd., are the contractors for the Beannachran dam. Messrs. A. A. Stuart & Sons (Glasgow), Ltd., are the contractors for the Aigas and Kilmorack dams.

Loch Awe Scheme.

Some of the civil engineering contracts for the Loch Awe hydro-electric works were awarded in the autumn of 1959. Part of this scheme will be the first large pumped-storage plant to be constructed in



Fig. 4.—Lubreoch Dam.

Scotland. The scheme is in three parts. The works of the Inverawe section will regulate the level of the water in Loch Awe by a low barrage at a short distance downstream from the outlet of the loch, the level of which will not be raised. From the barrage, where there will be a fish-pass, the water is taken through a tunnel to a power station.

The Cruachan section includes the pumped-storage plant where electrical energy from the nuclear-power and steam-operated stations at periods of low load

will be used to pump water from Loch Awe up to a high-level reservoir.

The Nant section includes the raising of the level of the water in Loch Nant by the construction of a dam near the outlet of the loch.

The consulting engineers for the Inverawe and Cruachan sections are Messrs. James Williamson & Partners, Glasgow, and for the Nant section, Messrs. Babbie, Shaw & Morton. The first contract for the Inverawe section has been placed with Messrs. George Wimpey & Co., Ltd.

A Prestressed Bow-string Pipe-bridge.

THE erection of a pipe-bridge (*Fig. 1*) with a span of 210 ft. over the River Tees at Eaglescliffe was completed in 1959 for the Tees Conservancy Board. It is a bow-string structure constructed of precast blocks which were prestressed after erection. The width of the deck, which carries two 33-in. water-mains and also provides a walkway, is 15 ft. The width

When the leading bogie was over the central temporary pier the Bailey bridge was floated out on pontoons and into position over the other half of the river. The concrete bridge was hauled across the remaining width of the river, moved sideways into a position above the abutments which had been constructed in advance, and lowered by jacks on to roller bearings.




Fig. 1.

of the arch boom is generally 7 ft., but bifurcates near each springing.

The structure was constructed and prestressed on the river bank, and was moved into its position across the river. A Bailey bridge was erected at one side of the site so that it extended over half the width of the river, and was supported on a temporary pier in the middle of the river. The prestressed concrete structure, mounted on bogies, was hauled by winches along the top of the Bailey bridge.

The total cost of the structure, including the piers and other foundations, was £54,000, of which £17,000 was for the superstructure and £2000 for the hand-rails and finishes. The contractors were the Dowsett Engineering Construction Co., Ltd., who collaborated in the design with the British Reinforced Concrete Engineering Co., Ltd. The prestressing was by the Gifford-Udall method, and the precast blocks were made by Dow-Mac Products, Ltd.

The Best **BIG** British **BAR BENDER** DIESEL OR ELECTRIC



Bending a single heavy bar



Bending a group of heavy bars
to a large radius



Bending a group of small bars
to a small radius

For the fastest and most accurate bending of single bars up to 2 inches diameter or a group of bars of combined cross-sectional area of 3 sq. inches, this machine, available with diesel engine or electric motor, has a world-wide reputation.

*** FOR SALE OR HIRE**

ACROW

Send for full descriptive brochure, prices and hire rates to:—

ACROW (ENGINEERS) LTD., SOUTH WHARF, LONDON, W.2 : Tel. AMB 3456 (20 lines)

Branches at: Belfast • Birmingham • Bristol • Cardiff • Glasgow • Leeds • Liverpool
Manchester • Newcastle • Saffron Walden • Southampton



Throughout the U.K. the Blue Circle Group of Companies has 29 cement works and 30 manufacturing plants at which are produced Blue Circle, Pelican and Dragon brands of Portland Cement, Ferrocrete, '417' Cement, Aquacrete, Sulfacrete, Hydracrete, Walcrete, Snowcrete, Colorcrete, Hydralime, Whiting, Super Snowcem, etc. It has 16 district offices and a network of distribution centres. The road transport owned by the Group includes over 1,200 vehicles for delivery in bag or in bulk, and it

operates one of the largest fleets of tugs and lighters on the Thames and Medway.

The Blue Circle Group is the largest cement manufacturing organisation in the world. You are invited to make use of its many services and profit from its great resources.

Blue Circle Products are exported to countries all over the world and the Group also has interests in twelve works overseas, nine of which are in the Commonwealth.



The Cement Marketing Company Limited,
Portland House, Tothill Street, London, S.W.1. Telephone ABBey 3456
G. & T. Earle Limited, Hull. Telephone HULL 16121
The South Wales Portland Cement & Lime Co. Ltd., Penarth, Glam.
Telephone Penarth 57301-4

A Tunnel Lining with Dry Joints.

In Figs. 1 and 2 is illustrated a method of lining a tunnel with precast segments adopted for the water main from Hampton (Middlesex) to Chingford (Essex). The main, tunnelling of which was recently completed by the Metropolitan Water Board, is 19 miles long and has a diameter of 8 ft. 6 in., and is at such a depth that water will flow through by gravity. Several shafts of 12 ft. diameter are provided for the purposes of construction and inspection, and range in depth up to 192 ft. The shaft at the eastern terminal is 67 ft. 6 in. in depth and 25 ft. in diameter and accommodates the pumps which raise the water from the tunnel to the reservoirs. It will at first convey 70,000,000 gallons of water daily, but it is possible to increase the capacity up to 120,000,000 gallons daily.

The tunnel was constructed in sections each of which formed a separate contract, and is lined with segments which mainly have the shape and dimensions shown in Fig. 3, and are wedged together as shown in Fig. 2. The segments were made with sulphate-resistant cement.

The segments, which are called "Don-segs", were precast in a yard where more than 400,000 were made and were delivered to the working sites at a rate of 400 to 500 rings per week; each ring comprises twelve segments.

The method of construction, which it is claimed was used for the first time in this country for this tunnel, incorporates some novel features, including the lining which eliminates bolting and grouting, and an excavating shield which combines the operations of boring the tunnel and expanding the segments into position. The shield attained speeds in excess of 250 ft. per week, which greatly exceeds that obtained by the conventional method using bolted iron segments as used in London tube railways and is several times faster than the rate generally achieved on main drainage works.

The shield excavated the firm clay, in which the tunnel is bored, and formed a cavity of about 10 ft. diameter to suit the lining without having to place filling behind the lining. The segments, which are mainly interchangeable, were placed loosely by hand on temporary templates




Fig. 1.—Concrete Segments forming Linings.




Fig. 2.—Segments before Ramming.




Fig. 3.—Precast Segment.

to form a ring comprising twelve segments, which were then wedged tightly together by means of twelve hydraulic rams acting from the shield. The surface of the lining was then sprayed with $\frac{1}{2}$ -in. cement mortar which was trowelled smooth by a mechanical process.

The work was carried out under the general direction of the Chief Engineer to the Board, Mr. W. M. Lloyd Roberts, and his predecessor, Mr. H. F. Cronin, C.B.E., M.C. The consulting engineers were Sir William Halcrow & Partners. The main contractors for the tunnel were Messrs. Kinnear, Moodie & Co., Ltd., who made many of the segments; the remainder were made by Stent Precast Concrete, Ltd. The contractors for the shafts and other works were Messrs. William Press & Son, Ltd., and Messrs. A. Waddington & Son, Ltd. The spraying of the lining was done by the Turiff Construction Corporation, Ltd.

[A description of an experimental tunnel 1000 ft. long which preceded the construction of the entire works was given in this journal for April, 1954, based on a paper by Mr. P. A. Scott in the Proceedings of the Institution of Civil Engineers, May, 1952. Each ring in this tunnel comprised ten segments (as shown in Figs. 1 and 2).

Another method of lining tunnels with concrete segments without bolting or grouting is to be used for an experimental railway "tube" tunnel to be driven by London Transport Executive in north-east London. The segments are erected to form a ring into a gap in which a key-segment is forced. The contractors for this trial work are Messrs. Kinnear, Moodie & Co., Ltd. A similar method, which was used for the new main-line railway tunnels at Potters Bar, Herts., is described in this journal for May, 1958.]

Concrete Roads in the U.S.A.

STATISTICS published annually by the U.S. Bureau of Public Roads show that the total length of concrete roads in the U.S.A. was about 95,000 miles in 1942 but only about 75,000 miles in 1957, although during this period about 19,000 miles of concrete roads were constructed. According to the latest figures available* the total length of surfaced roads in the forty-nine States exceeded 600,000 miles, so that the length of concrete roads was about one-eighth of the total at the end of the year 1957. About 2000 miles of concrete roads were constructed during 1957, including about 380 miles of new roads or earthen roads paved with concrete, about 1000 miles of old concrete roads resurfaced with concrete, and about 500 miles of existing roads having other surfaces that had been changed to concrete. Because about 4000 miles of concrete roads had been changed to other types of surfacing, mainly bituminous or asphaltic, there was a reduction during the year of about 2000 miles of roads with concrete surfaces.

The exact lengths of each type of road are not available because the lengths of roads paved with bricks or blocks are included in the lengths of Portland-cement concrete roads and the data on changes of types of road do not indicate whether the bituminous or asphaltic surfaces were

applied to existing concrete roads or whether the concrete roads were replaced entirely by another form of construction. Also, information on roads having a lean concrete sub-base surfaced with bituminous or similar materials is separate.

In 1958 the cost of concrete roads was about 50 per cent. higher than in 1946 and had remained almost unchanged since the middle of 1956. Comparison with costs in previous years, and especially before 1940, is not possible because of the more stringent requirements in the later years. In the period from 1946 to 1958 the cost of excavation increased by about 15 per cent., whereas the cost of reinforced concrete structures such as bridges had increased 62 per cent. by 1957 but fell to about 53 per cent. in 1958.

Symposium on Grouting.


THE date of the Symposium on Grouting Prestressed Concrete, which is being organised by the Fédération Internationale de la Précontrainte and R.I.L.E.M., has now been changed to January 5 to 7, 1961. As previously announced, the Symposium will be held at Trondheim, Norway, and the programme is not altered. Contributions of papers should be sent to Professor I. Lyse, Norges Tekniske Høgskole, Trondheim, Norway, and should reach him before August 15.

* "Highway Statistics, 1957." Published in 1959 by the U.S. Department of Commerce.

**THE DESIGN AND SUPPLY
OF THE ENTIRE FORMWORK
FOR THE PRECAST UNITS FOR**

DUNGENESS LIGHTHOUSE

WERE ENTRUSTED TO US



One of the first complete formworks leaving our new works en route to the works of Spun Concrete Ltd., who are responsible for the precasting programme of this lighthouse. Architects and Engineers: Messrs. Ronald Ward & Partners. Contractors: Taylor-Woodrow Construction Ltd.

YOU TOO CAN DEPEND ON US

STELMO

*the most comprehensive
mould service in the world*

STELMO LTD. · WESTWELL LEACON · CHARING · ASHFORD · KENT. Tel: Charing 395-7

Pipe-jointing

STRONG WATERTIGHT JOINTS

IN THE MINIMUM OF TIME*

*
within a few hours drains can be smoke-tested
or water-tested and trenches filled in

no other type of cement gives such
SOUND AND SPEEDY RESULTS



The Cement for Industry

LAFARGE ALUMINOUS CEMENT CO. LTD.

73 BROOK STREET, LONDON, W.1. TEL: MAYfair 8546

Deterioration of Concrete due to Alkali Reaction.

OBSERVATIONS of the deterioration of concrete structures have led to the discovery during the last decade that this is sometimes caused by a chemical reaction between the alkalis present in cement and soluble silica which is present in certain aggregates. Most British aggregates are inert but some European and American aggregates are not. A committee appointed in Denmark in 1953 to study the problem has issued two interim reports* from which these notes are abstracted.

The alkali reaction occurs between cement with a high content of alkali and aggregates containing soluble silica, when alkaline hydroxide reacts with the silica and



Fig. 1.

* Committee on Alkali Reactions in Concrete. Progress Reports N.1 (1956) "Disintegration of Field Concrete", by G. M. Idorn, and L.1 (1957) "Investigation of the Effect of Some Pozzolans on Alkali Reactions in Concrete", by A. H. M. Andreassen and K. E. Haulund Christensen. Copenhagen: The Danish National Institute of Building Research. Price 12 Kroner each. Printed in the English language.

April, 1960.




Fig. 2.

water to form an expansive gel. If sufficient water and alkali are present the gel is eventually transformed into a solution of alkaline silicate. The reaction produces a measurable expansion of the concrete, cracks and fractures, craters in the surface, exudations of resin-like gel, and efflorescent deposits.

EXPANSION.—Expansions of 0.5 to 0.7



Fig. 3.

per cent. are known to have occurred during periods of 14 to 15 years. The rate of expansion is greater in summer than in winter.

FRACTURES.—Cracks and fractures are invariably present. Cracking is frequently observed, and is often accompanied by spalling. Long wide cracks occasionally occur. The deterioration of the staircase shown in Fig. 1 took place in seven years, during which time the treads were re-surfaced with mortar.

CRATERS.—Particles of chemically-active aggregate which occur near the surface of the concrete may cause the formation of craters. Fig. 2 shows a crater which appeared in a jetty 25 years after it was built. The photograph was taken fourteen days after the surface




Fig. 4.

TABLE I.

CAUSE OF DETERIORATION	EVIDENCE OF DETERIORATION				
	EXPANSION	CRACKING	CRATERS	EXUDATIONS	DEPOSITS
ALKALI REACTION	FREQUENT	PATTERN CRACKS INVARIABLE SPALLING OCCASIONAL	FREQUENT	FREQUENT	FREQUENT
FROST	VERY RARE	SPALLING FREQUENT PATTERN CRACKS RARE	FREQUENT	NONE	FREQUENT
SEAWATER ATTACK	NONE KNOWN	SPALLING FREQUENT PATTERN CRACKS RARE	NONE	NONE	FREQUENT

was painted, when the crater was not present. Craters are always formed as a result of the development of gel.

EXUDATIONS OF GEL.—These occur frequently as drops up to 1 in. diameter on ceilings and walls, and as craters up to $\frac{1}{4}$ in. diameter on floors. Old deposits are usually white and dry. Fresh deposits are usually watery, viscous or hard, yellow or brown in colour, and resin-like in appearance. Fig. 3 shows a fresh drop

7 mm. in diameter, surrounded by older deposits.

SECONDARY DEPOSITS.—Deposits of calcium carbonate often occur on surfaces, forming stalactites under ceilings and beams (Fig. 4).

Some of these symptoms may also appear in concrete which has been damaged by frost or sea-water. Table I gives a comparison of the effects produced by each of these causes.

IMPERIAL COLLEGE OF SCIENCE AND TECHNOLOGY

Bursaries in Concrete Technology

Bursaries of £460-£760 according to experience are available for Session 1960-61. Candidates must hold a degree in engineering and have a good knowledge of the theory of structures. Full information from the Registrar, Imperial College, London, S.W.7.


Closing date, June 1st, 1960.

THE UNIVERSITY OF LEEDS

The University offers a one-year full-time course for a Diploma in Concrete Technology commencing in October, 1960. The course consists of lectures, laboratory work and a design or research project.

Applications for admission to the course are invited from graduates and from holders of equivalent qualifications in engineering. Preference will be given to applicants who have had one or two years' practical experience.

Further information may be obtained from the REGISTRAR, The University, Leeds, 2.



**One floor of 13,500 sq. ft.
per seven days—**

**OMNIA Concrete Floors
contributed to remarkable
construction speed in this
major London office building**



Friars House, Blackfriars, London,
occupied by Central Electricity Generating Board
Architect: Robin Selfert, F.R.I.B.A.
Quantity Surveyors: Thompson & Alexander
Consulting Structural Engineers: Reinforced Concrete Steel
Co. Ltd.
Contractors: George Wimpey & Co. Ltd.

Friars House, London, has a total of 90,000 sq. ft. of OMNIA Floors on eight floors, using 29 ft. spans with a live load of 120 lb./sq. ft. Spine beams are contained within the depth of the floor, giving clear soffits without any projecting beams. Erection was completed at the rate of one floor per seven days—a typical OMNIA success story. The OMNIA Floor combines precast and in-situ methods of construction, and appeals particularly to the Architect because it spans economically to over 30 feet and gives a level and unbroken soffit without camber or bowing.



**Light in weight, yet monolithic
Needs no shuttering
Easy to transport and handle
Quick and simple to erect
Spans to over 30 ft.—no camber or bowing
Economical in manufacture and installation
Adaptable in design and for services**

OMNIA CONSTRUCTIONS LIMITED, 121 London Wall, London E.C.2. Monarch 2272/6


The OMNIA Concrete Floor is available in all parts of the country from 15 OMNIA Licensees:

THE ATLAS STONE CO. LTD., LONDON
THE BLOKCRETE CO. LTD., SOUTHAMPTON
F. BRADFORD & CO. LTD., EDMONTON
BRADLEYS (CONCRETE) LTD., DARLASTON
G. W. BRUCE LTD., ABERDEEN
T. C. CAMPBELL LTD., NOTTINGHAM
COWLEY CONCRETE CO. LTD., ABERGON

DERWENT CAST STONE CO. LTD., MALTON
DUNBRIK (YORKS) LTD., LEEDS
EDENHALL CONCRETE PRODUCTS LTD.,

PENRITH
HYDRAULIC PRECASTS LTD., NORWICH
JAMES E. MILLAR LTD., FALKIRK
PRESTATYN PRECAST CONCRETE CO., LTD.,
PRESTATYN
ST. IVES SAND & GRAVEL CO. LTD., HUNTS
SAMUEL TYZACK & CO. LTD., SUNDERLAND

Multi-wire strand For prestressed concrete



This photograph shows the stressing of multi-wire "Bridge" Strand at the Perth Narrows Bridge in Australia. "Bridge" Strand is made from Somerset Wire.

CONSULTING ENGINEERS: G. Maunsell & Partners
PRESTRESSED CONCRETE CONSULTANT: E. W. H. Gifford
CONTRACTORS: Christiani & Nielsen Ltd.

IF YOU WANT TO PUT STEEL INTO CONCRETE
GET IN TOUCH WITH

GKN Reinforcements Ltd

197 KNIGHTSBRIDGE, LONDON, S.W.7. KENsington 6811

SMETHWICK, BIRMINGHAM (Smethwick 1991) • MANCHESTER (Ardwick 1691)
GLASGOW (Bell 2444) • MIDDLESBROUGH (3843) • CARDIFF (Cardiff 45220)
BRISTOL (Bristol 21555) • LEICESTER (Leicester 25114) • LEEDS (Leeds 27311)
WORKS AT CARDIFF, SMETHWICK, WIGAN & GLASGOW

Accidents on Construction Work.

An accident that occurred recently during the course of construction of a steel bridge in the north-west of England brought attention to the fact that although there are strict safety regulations in the building industry there is none for civil engineering. The Minister of Labour announced in the House of Commons recently that it was proposed to extend the definition of "work of engineering construction" in the Factories Act to include most civil and constructional engineering.

In a "Report on Safety and Health in the Building and Civil Engineering Industries (1954 to 1958)" issued by the Minister of Labour in February, 1960 (and obtainable from Her Majesty's Stationery Office; price 1s. 6d.), it is stated that the number of accidents in 1958 reached the highest ever recorded. Two-thirds of the fatal accidents and nearly half of all accidents in building in that year, were due to falls of persons.

Details of some actual accidents are given in the number for January, 1960, of a quarterly publication entitled "Accidents: How they happen" (obtainable from Her Majesty's Stationery Office; price 1s. 3d.). This review deals with accidents in factories, on building sites and on works of engineering construction.

The Federation of Civil Engineering Contractors last year organised training courses for the promotion of safety. These are held in collaboration with the Ministry of Labour, in North London and Birmingham, but similar courses are being arranged to be held at Liverpool, in South Wales, and in Scotland. The syllabus is such that it is suitable for supervisors down to the level of ganger, and for young engineers. The subjects dealt with include the causes of accidents, tidiness on sites, excavations and earthworks, staging, electricity, lifting and carrying, and the cost of accidents. Dates of the courses can be obtained from the Federation at Romney House, Tufton Street, London, S.W.1.

Accidents in the Building Industry.

The following is a summary of a talk on "Preventing Falls in the Building Industry" given by Mr. J. A. Hayward at

the National Industrial Safety Conference held at Scarborough last May.

Accidental falls in the building industry were causing some concern so long ago as 1858, in which year "The Builder" reported that the number of cases of falls treated at London hospitals in one year was not likely to be less than 15,000 and that a very large proportion of the sufferers were in the building trades. During recent years there have been an average of 15,000 accidents reported annually in the building industry and, of these, about 200 have been fatal. Although there was substantial improvement in the immediately preceding years, the number in 1958 was a little greater than the average of the past three or four years. About 86 per cent. of all fatal building accidents and about 50 per cent. of reportable injuries are the result of falls.

The casual nature of the building work makes it difficult to apply safety training schemes such as can be undertaken in many other industries. Men are subject to the vagaries of the weather. When a man has spent several hours on a building site, probably wet, cold, and tired, he may not be in a frame of mind to plan the safest way of doing a job, and this may be the reason why the accident rate is perhaps greater than in some other industries. If management and men take elementary precautions to see that safety regulations are complied with, many falls which now occur could be prevented. In one civil engineering and building firm where such precautions have been enforced less than 25 per cent. of the fatal accidents have been a result of falls, and of reportable accidents about 20 per cent. have been due to falls compared with the average of about 50 per cent. for the industry as a whole.

A Guide to Safety.

A booklet entitled "Organise for Safety" was published recently by the National Federation of Building Trades Employers and gives guidance to building firms on the formulation and application of a policy for the prevention of accidents.

The correct methods of erecting and maintaining scaffolding, operating cranes and lifting appliances, and guarding openings are well known, but the object of the

booklet is to show how the determination of the management to reduce the number of accidents may be translated into taking effective precautions by the development of a chain of responsibility the members of which include safety officers, agents, general foremen, trades foremen, gangers and other employees, each of whom must be clearly instructed as regards their personal responsibilities. The recommenda-

tions can be applied in principle by all building firms irrespective of their size since, while the complete safety organisation may not be appropriate to a small firm, the principles can be applied with such modifications as may be necessary to suit particular circumstances. Copies of the booklet are obtainable from the Federation, 82 New Cavendish Street, London, W.1 (price 2s. 6d. post free).

Disposal of Unwanted Mixed Concrete.

A SUPPLIER of ready-mixed concrete in Washington, U.S.A., has installed a machine in which the aggregate is recovered from mixed concrete that is left over at the end of the day. The machine is in the form of an inclined horizontal rotating drum in which is a screw conveyor. While it is in the transit-mixer water is added by the driver until the concrete has a slump of 10 in. or so. This material is tipped into the higher end of the drum in batches of $\frac{1}{2}$ cu. yd. to $\frac{3}{4}$ cu. yd. The rotation of the drum stirs the material so that the cement and water and the finest sand are passed along the drum and out at the lower end. The screw-conveyor then transports the aggregate to the discharge end of the drum while it is sprayed with water to remove any remaining cement. After leaving the drum the aggregate is passed over screens and separated into coarse and fine material for re-use. It is stated that the aggregate so recovered is of the same grading as the original mixture except for the loss of some of the finest particles. The capacity of the machine is about 10 cu. yd. per hour. The water and cement are stored in sumps until the sludge has settled to the bottom, and the sludge is then scooped out and dumped into a worked-out part of the gravel pit.

Partnership.


MR. E. W. H. GIFFORD has taken Mr. J. R. Lowe and Mr. H. E. Lewis into partnership. The consulting engineering practice will henceforth be carried on under the name of E. W. H. Gifford and Partners.

Reinforced Lightweight Concrete.

RESEARCH on reinforced lightweight concrete at the Building Research Station was extended in the year 1958 to include aerated concrete as well as concrete made with foamed slag, expanded shale or clay, and sintered pulverised-fuel ash. Many specimens exposed in severely polluted atmospheric conditions for a year were broken open; corrosion due to exposure could not be observed on any of the bright mild-steel bars embedded in the specimens. Pull-out tests and tests on beams of lightweight concrete show that the bond strength was about one-half to three-quarters of the bond strength of gravel concrete having the same compressive strength. The bond of bars in a horizontal position during casting was only about one-half of the bond of vertical bars. The deflections, at working loads at mid-span of the lightweight concrete beams though somewhat greater than those of gravel concrete, were not considered to be excessive. The combined effect of shrinkage and creep on the deformation of shallow beams subjected to loading of long duration is such that the maximum deflections of lightweight concrete beams are greater than those of beams made with gravel concrete by between about 15 and 50 per cent.—"Building Research 1958." H.M. Stationery Office. Price 5s. 6d.

Brochure Received.

A NEW booklet entitled "Asbestos and Asbestos-Cement Products" deals with asbestos as a raw material, and asbestos-cement products, and gives notes on the properties and methods of using such products. The booklet is obtainable free from Turners Asbestos Cement Co., Ltd., Trafford Park, Manchester 17.



333 Simplex Cast-in-situ Concrete Piles were used in the foundations of the Municipal College Extensions in Anglesey Road, Portsmouth

Architect to the City of Portsmouth: F. Mellor, Esq., F.R.I.B.A.

SIMPLEX CONCRETE PILES LTD.

190 PALACE CHAMBERS,

BRIDGE STREET,

WESTMINSTER, S.W.1

Telephone: Trafalgar 1167-9

MISCELLANEOUS ADVERTISEMENTS.

Situations Wanted, 5d. a word : minimum, 12s. Situations Vacant, 6d. a word : minimum, 15s. Other miscellaneous advertisements, 6d. a word : minimum, 15s. Displayed advertisements, 40s. per column inch. Box number 1s. extra.

Advertisements must reach this office, 14 Dartmouth Street, London, S.W.1, by the 23rd of the month preceding publication.

SITUATIONS VACANT.

SITUATIONS VACANT. Civil Engineering Assistants required for site work on contracts. The work is varied and interesting with opportunities for promotion and study of new methods. Applicants should be between the ages of 25 and 32, and hold a degree in civil engineering or equivalent. They should have had a minimum of 3 years with a contractor on site work, which must have included setting-out and progress measurement. Experience in design of formwork and other temporary works, control of concrete quality would be an advantage. Apply in writing, giving brief details of qualifications and experience, also stating age, and salary required, to **THE CHIEF ENGINEER, THE DEMOLITION & CONSTRUCTION CO. LTD., 3 St. James's Square, London, S.W.1.**

SITUATIONS VACANT. Consulting engineer, Westminster, invites applications from detailer/draftsmen with a minimum of four years' experience in reinforced concrete. Salary scales appropriate to experience and ability. Non-contributory pension and bonus schemes in operation. Holiday arrangements will be honoured. Apply in writing, giving full particulars, to Box 4650, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

SITUATIONS VACANT. Junior Civil Engineers required to work on sites with excellent opportunities for training. Applicants should be graduates or equivalent and should be between the ages of 20 and 26. Apply in writing, giving brief details of qualifications and experience (including vacation course work), also stating age, to **THE CHIEF ENGINEER, THE DEMOLITION & CONSTRUCTION CO. LTD., 3 St. James's Square, London, S.W.1.**

SITUATIONS VACANT. Reinforced concrete detailers and designers required in North West London. Three-weeks' paid holiday, and excellent prospects in small expanding firm. Telephone Maida Vale 7890.

SITUATIONS VACANT. Structural and civil engineers require for their Bristol office senior and intermediate designer-detailers experienced in either (1) reinforced concrete, or (2) structural steelwork. Excellent opportunities in an expanding organisation for the right men. Positions are pensionable, and offer first-class experience. Box 4659, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

SITUATION VACANT. Engineering assistant required to organise small design office specialising in prestressed concrete work. Imagination and initiative essential. Attractive salary, good prospects. Write, giving full particulars, to **PRESTRESSED SALES LTD., 64-66 Battersea High Street, London, S.W.11.**

SITUATIONS VACANT. Structural engineers. Engineers required in Architect's Department, L.C.C. Up to £1,135 (under review). (a) *Structural Engineering Division*—Extensive programme includes multi-storey flats, schools, offices, warehouses and other buildings. (b) *Structural Engineering Division*—To deal with applications in respect of special structures under Part IV of London Building Act (A) Act, 1939, and constructional by-laws. Interesting work involving consideration of unconventional forms of construction. (c) *District Surveyors' Service*—Work mainly outside involving negotiations with Architects, Engineers, and Surveyors, and supervision of works in progress. Good prospects in all these aspects of the Council's work. Application form and particulars from **HUBERT BARNETT, F.R.I.B.A., Architect of Council, (EK/CCE/495/4), County Hall, London, S.E.1.**

SITUATIONS VACANT. D. W. COOPER requires designer/draftsmen experienced in reinforced concrete and/or steelwork and/or timber engineering. Apply in writing to 265 Westmorland Road, Newcastle-upon-Tyne, 4, stating age, qualifications, and marital status.

SITUATIONS VACANT. Reinforced concrete designer/detailers and detailers required in Hammermith office of consulting engineers. High salaries and good prospects, with interesting work. Five-days' week, pension scheme, holiday arrangements honoured. Apply in confidence, with full details of experience, and salary required, to **ALAN MARSHALL & PARTNERS, Federal House, 2 Down Place, London, W.6. Telephone Riveride 8771.**

SITUATIONS VACANT. Assistant designer/detailers, detailer/draftsmen, and trainee/draftsmen required for interesting work on varied types of reinforced concrete structures. Five-days' week. Luncheon vouchers. Apply, with usual details, to **JOHN F. FARQUHARSON & PARTNERS, Chartered Structural Engineers, 34 Queen Anne Street, London, W.1. Telephone Langham 6681.**

ASSISTANT DESIGN ENGINEERS AND DRAUGHTSMEN

required for design and detailing of reinforced concrete structures.

A range of appointments offer excellent prospects to both qualified men and those who are studying for qualifications.

Five-days' week. Superannuation scheme.

Apply, stating age, qualifications and experience, to **PERSONNEL MANAGER (A.D.E.4), JOHN LAING AND SON LIMITED, London, N.W.7.**

G.K.N. REINFORCEMENTS LIMITED

have vacancies in their Birmingham Drawing Office for Reinforced Concrete Designers and Detailers, also Draughtsmen and Draftswomen who would have opportunities for training as Detailers. Five-days' week, pension scheme, staff canteen. Write to **CHIEF ENGINEER, G.K.N. REINFORCEMENTS LTD., Alma Street, Smethwick 40, Staffs, or 'phone Smethwick 1991.**

NATIONAL RESEARCH COUNCIL, CANADA DIVISION OF BUILDING RESEARCH SCIENTIFIC RESEARCH OPPORTUNITY

The Division of Building Research, National Research Council, has an opening for a Chemist or Chemical Engineer to assume responsibility for cement and concrete research in the Division. The research studies will embrace studies on the properties and use of concrete materials in well-equipped laboratories located in Ottawa.

Applicants should hold a Master's degree from a recognised university and have from 3 to 5 years' experience in the cement or concrete field.

Salary will depend on education and experience. Applications and requests for further information should be addressed to:

Employment Officer,
National Research Council,
Ottawa 2, Ontario,
Canada.

CIVIL ENGINEERING DRAUGHTSMEN

required for design of reinforced concrete structures and foundations, steel structures and brick buildings, in connection with heavy Engineering and Chemical Industry. Applicants should have relevant academic qualifications up to at least N.C. standard and sufficient experience to enable them to prepare drawings from verbal and briefly-sketched instructions. A knowledge of site surveying and levelling is also necessary. Write for application form to PERSONNEL MANAGER, IMPERIAL SMELTING CORPORATION LIMITED, Avonmouth, Bristol, quoting reference CD/CCE.

CONSULTING ENGINEERS

offer permanent, pensionable (if desired) posts to those really interested in advanced structural design, draughtsmanship and building techniques. The structures, large and small, in most cases have strong architectural interest as well, and the materials used are as varied as the structures: concrete, brick, steel and timber, with strong emphasis on concrete, reinforced or stressed. Applicants should be qualified and experienced as appropriate to the various grades offered, and those keen to learn will have ample opportunities of doing so both in the office and on the site during construction.

Pleasant working conditions in friendly atmosphere in new modern offices in Hammersmith (from mid-April). Five-days' week with good holidays (current year as well). In addition to the basic salary, generous annual bonuses are paid rewarding efficiency and hard work directly related to individual effort. Luncheon vouchers, car allowance and travelling expenses between home and office are paid in addition to basic salary.

Jobs are available in the following grades:

1. Senior Assistant Engineer. Preferably with good University degree and professional qualifications. Approximately 7 years' experience at least, and age limits of 30 to 40 preferred. Basic commencing salary in the range of £1050 to £1300.
2. Junior Engineers. Newly qualified with good University degree and little or no experience. Opportunity to gain site experience. Basic commencing salary between £600 and £700.
3. Experienced draughtsmen with 5 to 10 years' drawing office experience, preferably with some knowledge in and aptitude for design. Help will be given to those studying for professional examinations, with opportunities (as they occur) to gain necessary site experience. Age between 23 and 35 with approximate basic salary range of £750 to £1100.

Please write or telephone for interview to:

CHARLES WEISS AND PARTNERS

1 WANDSWORTH ROAD
LONDON, S.W.8
RELIANCE 7011

or after mid-April 1960 to:

123 King Street, Hammersmith, London, W.6.
(Riverside 7843)

Travelling (and hotel if necessary) expenses incurred for attending interview will be refunded.

SITUATIONS VACANT. Consulting engineers have vacancies for reinforced concrete detailers, and designer-detailers. Salaries in accordance with experience. Luncheon vouchers. Apply in writing to BYLANDER, WADDELL & PARTNERS, 165 Wembley Park Drive, Wembley, Middlesex.

SITUATION VACANT. W. & C. FRENCH LTD. urgently require designer/detailer mainly for reinforced concrete design and detailing. Applicants must be keen to learn about new methods and types of construction. Apply in writing, stating age, salary required, and full details of experience, to PERSONNEL MANAGER, 50 Epping New Road, Buckhurst Hill, Essex.

SITUATIONS VACANT. Designer-detailers and draughtsmen experienced in reinforced concrete required for interesting work on nuclear power stations. Apply, in writing, to the CHIEF ENGINEER, NUCLEAR CIVIL CONSTRUCTORS, 53 Carnaby Street, London, W.1.

SITUATIONS VACANT. Reinforced concrete designers and detailers required. Good opportunities for advancement in new company. Apply ENGINEERING, DESIGN & CONSTRUCTION CO. LTD., Archibald House, Empire Way, Wembley. Telephone Wembley 9474.

SITUATION VACANT. Senior qualified design engineer for consulting engineers' London office, to take charge of reinforced concrete section for blocks of offices, hospitals, etc. Write, stating experience, and salary required, to Box 4659, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

SITUATIONS VACANT. A consulting engineer, intending to expand his activities, requires senior engineer, a number of designers, design-detailers, and draughtsmen. Very good prospects and salary, but only first-class men will be considered. Please apply, stating age and experience, to Box 4658, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

BRC

**Experienced
Reinforced
Concrete
Designer / Detailers
and Draughtsmen
Wanted
for our Stafford,
London & Provincial
Design Offices**

Apply

Chief Engineer: A. P. MASON,
B.Sc., M.I.C.E., M.I.Struct. E., M.ASCE.
THE BRITISH REINFORCED CONCRETE
ENGINEERING CO. LTD., STAFFORD

SITUATION VACANT. Structural engineer required experienced in reinforced concrete with particular reference to multi-storey structures, and preferably some knowledge of prestressed concrete. Candidates must be qualified and capable of preparing preliminary designs and estimates. Five-days' week, and superannuation scheme in operation. Apply, giving details of age, experience, and salary required, to **OFFICE MANAGER, THE EXPANDED METAL CO. LTD., P.O. Box 14, West Hartlepool, Co. Durham.**

SITUATION VACANT. London concrete products company needs engineer/designer with experience of all types of mould design. Salary £1500 per annum, plus car and possibility of directorship. Write, giving full details of experience, to **Box 4662, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.**

SITUATIONS VACANT. Draughtsmen. Reinforced concrete designer/detailers required. Write **WELLESLEY CO. (LONDON) LTD., 349 Brixton Road, London, S.W.9.**

SITUATION VACANT. Structural engineer required for design and estimating of prestressed frame and reinforced concrete structures and hollow tile floorings. Accustomed to design and supervision of prestressed and post-tensioned concrete units. Please state age and experience. Salary according to qualifications and experience. Superannuation scheme. Write, addressing envelope "Personal", to **Managing Director, Box 4665, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.**

NUCLEAR CIVIL CONSTRUCTORS

(Trollope & Colls Ltd.—
Holland & Hannen and Cubitts Ltd.)

**SENIOR ENGINEER/AGENT
SENIOR QUANTITY SURVEYOR
WORK STUDY OFFICER
INCENTIVE SCHEME TARGET SETTER
CIVIL ENGINEERING ESTIMATOR
GENERAL FOREMEN
INSPECTOR CRANE & LIFTING APPLIANCES
ASSISTANT ENGINEER (Field)
ASSISTANT ENGINEER (Design Office)
BONUS CLERKS
DAYWORK CLERKS
ASSISTANT SURVEYORS
SECTION FOREMEN**

The above positions offer good opportunities for promotion to men with initiative and capable of accepting responsibility.

Applications, stating previous experience and qualifications, should be addressed to:

Services of the following staff are required at the Nuclear Power Station Contract, Trawsfynydd, North Wales, and in the London Head Office:

**Mr. T. J. Winter, Business Manager,
Nuclear Civil Constructors, Nuclear Power Station,
Trawsfynydd, North Wales.**

SITUATIONS VACANT. Consulting engineers require reinforced concrete detailers. Minimum three years' experience. Permanent positions. Pension scheme, luncheon vouchers. Send details of experience, and salary required, to F. R. BULLEN & PARTNERS LTD., Dacre House, Dean Farrar Street, Westminster, S.W.1.

SITUATIONS VACANT. Junior assistants wanted for consulting engineers' office. Apply in writing to W. E. J. BUDGEN & PARTNERS, 54 Queen Anne Street, London, W.1.

SITUATION VACANT. Reinforced concrete designer-draughtsman conversant with hollow tile floors, staircases, etc., required by specialist contractor in London. Write, giving brief particulars, and salary required, to BROADMEAD PRODUCTS LTD., 231 Strand, London, W.C.2.

SITUATIONS VACANT. Civil and structural. Graduate engineers and designer-draughtsmen required for all types of design works on large civil and structural engineering projects in the U.K. and overseas. Resident engineer positions also available. A high rate of earnings is paid in this firm to those with initiative and ability. London office of R. T. JAMES & PARTNERS, Consulting Civil Engineers, 6 Lower Grosvenor Place, London, S.W.1.

SITUATION VACANT. Senior engineer required for London professional office. Must have professional qualifications and at least five years' design experience in structural reinforced concrete. Knowledge of steelwork an advantage. Age limit 30-40. Candidates should be capable of handling contracts from start to finish, and able to control staff. The work is varied and offers scope for initiative. A good salary will be offered. Apply, stating experience, and salary required, to FARMER AND DARR, Romney House, Tufton Street, London, S.W.1.

SITUATIONS VACANT. Reinforced concrete detailers required for London professional office. The work is varied and offers opportunities for gaining design experience. Excellent prospects for men wishing to advance. Five-days' week. Please apply, giving full details, to FARMER AND DARR, Romney House, Tufton Street, London, S.W.1.

LAING

AGENTS

are required for senior appointments on large construction contracts in various parts of the country.

Applicants will be required to have a sound experience on a wide variety of contract work. L.I.O.B. or A.M.I.C.E. qualifications preferred. Age 30-40.

These appointments offer progressive and permanent employment with superannuation scheme.

Salary will be commensurate with experience and qualifications.

Apply in writing to PERSONNEL MANAGER (A-5), JOHN LAING AND SON LIMITED, London, N.W.7.

SITUATIONS VACANT. Designer-detailers required for permanent positions by consulting engineer. Work ranges from structural frames to prestressed concrete bridges and structural steelwork. Work in London only, but site visits elsewhere. Scope for advancement. Assistance towards A.M.I.C.E. or A.M.I.Struct.E. Write for appointment. DOROVAN H. LEE, 66 Victoria Street, London, S.W.1.

SITUATIONS VACANT. Design engineers and draughtsmen required for extensive reinforced concrete heavy foundation work in S. Wales. Write, giving age, experience, etc., to BOX 4661, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

SITUATIONS VACANT. Reinforced concrete draughtsmen required for contractor's office in Westminster. Applicants, age 25-35, must have had at least five years' experience in detailing with firm of repute. Written applications only, giving details of experience, to TILEMAN & Co. LTD., Romney House, Tufton Street, London, S.W.1.

COVENTRY CORPORATION

require the following Staff in Civil and Structural Engineering Section of City Engineer's Department:—

(a) SENIOR ASSISTANT ENGINEER—APT V (£1220-1375),

commencing according to qualifications/experience. A.M.I.Struct.E. or other suitable qualification, and considerable experience of design and construction in reinforced concrete essential. Some experience of structural steelwork advantageous.

(b) ASSISTANT ENGINEERS—"Special" (£785-1070) or APT IV (£1065-1220),

commencing according to qualifications/experience. Previous experience of design and detailing reinforced concrete structures essential.

Programme of major development offers exceptional opportunities for experience of interesting and varied work. Housing accommodation may be available. Removal Expenses Loan (up to £30). Application forms from CITY ENGINEER, Council House, Coventry, returnable by 30th April.

CUBITTS

REINFORCED CONCRETE

DESIGNERS, DETAILERS AND DRAUGHTSMEN

are required for an immediate expansion of structural drawing office. The work will be interesting and involves the use of precast and prestressed concrete. Experience in these techniques will be an asset, but opportunity will be provided for training those who are interested and have some basic knowledge of reinforced concrete.

Please send full details to:—

Personnel Manager

**HOLLAND AND HANNEN
& CUBITTS**

(GREAT BRITAIN) LTD.

1 Queen Anne's Gate, London, S.W.1

SITUATIONS VACANT. Senior designers and detailers required experienced in reinforced concrete construction. High salaries offered. Permanent and progressive appointments. **NORRIS CONSULTANTS LTD.,** Beacon House, Queen's Road, Bristol, 8.

STRUCTURAL ENGINEERS REINFORCED CONCRETE DESIGNER/DETAILERS

required for design work in the rapidly-expanding field of multi-storey garage construction. Good prospects for men with ability. Write to the Personnel Officer, **UNIT CONSTRUCTION CO. LTD.,** Feltham, Middlesex.

OVE ARUP & PARTNERS

will shortly be opening design offices in the Croydon and Watford areas with vacancies for engineers and detailers experienced in structural work. Salaries in accordance with experience up to £1300 a year. Luncheon vouchers and staff pension scheme. Please write to 13 Fitzroy Street, London, W.1.

CIVIL ENGINEERING AND STRUCTURAL ASSISTANTS

(Intermediate and Senior)

Required with design or detailing experience in any of the following

- (a) Drainage and Sewage Purification Schemes.
- (b) General Civil and Structural Work, including steelwork or reinforced concrete.
- (c) Hydro-Electric works.
- (d) Water Supply.

Superannuation Scheme. Apply by letter, stating age, qualifications and experience, to **Babtie, Shaw & Morton, Chartered Civil Engineers, 17 Blythwood Square, Glasgow, C.2.**

SERVICES OFFERED.

SERVICES OFFERED. Experienced graduate engineer offers part-time services to consulting engineers. Fully equipped. Prompt attention and services assured. Box 4660, **CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.**

SERVICES OFFERED. Capacity available for consulting engineers for the design and detailing of all types of reinforced concrete and steel frame structures, heavy foundations, road works, etc. Drawing office services. Telephone **Tulse Hill 9195.**

SERVICES OFFERED. Qualified and experienced engineers offer consulting engineers a first-class service for all types of civil and structural works, including steel and reinforced concrete. Design and detailing. Box 4663, **CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.**

SERVICES OFFERED

Qualified Engineer wishes to undertake reinforced concrete design and detailing for Consultants. Box 4664, **CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.**

FOR SALE, WANTED OR HIRE.

FOR SALE. Steel guttering, ironwork, sheet metal work. **E. STEPHENS & SON LTD.,** Bath Street, London, E.C.1. Clerkenwell 1731.

FOR SALE. Unused 500-ton three-station hydraulic concrete slab press, with self-contained oil pumping unit. 400-ton Fielding & Platt three-station hydraulic concrete slab press, with self-contained oil pumping unit. 400-ton Fielding & Platt two-station hydraulic concrete slab press, with self-contained oil pumping unit. **REED BROTHERS (ENGINEERS) LTD.,** Repaint Works, Woolwich Industrial Estate, London, S.E.18. Telephone **Woolwich 7611 (6 lines).**

FOR HIRE. Lattice steel erection masts (light and heavy), 30 ft. to 150 ft. high, for immediate hire. **BELLMAN, 21 Hobart House, Grosvenor Place, London, S.W.1.**

"THE CONCRETE YEAR BOOK" 1960 EDITION

1288 pages

Price 10s. : by post 11s. 9d.
\$2.40 in Canada and U.S.A.

HANDBOOK

In this Section no attempt is made at giving individual opinions, but to present in concise and convenient form specifications or methods which are either standard practice or recommendations formulated after thorough investigations by competent bodies. Complete memoranda and data of everyday use.

DIRECTORY

The only complete Directory of the concrete industry, classified under different headings for ease of reference. Complete list of trade names and brands.

CATALOGUE

Describes the businesses or products of more than 900 firms connected with or catering for the concrete industry. Invaluable to anyone seeking a firm of contractors to carry out special kinds of work, or a machine, material or product for any purpose.

Make sure of your copy now.

**CONCRETE PUBLICATIONS LTD.,
14 DARTMOUTH STREET,
LONDON, S.W.1**

We know what it's like to wait

Tentor Bars are scarce. But so is the steel from which they are made. That, unfortunately, is the long and short of it. To those of our customers who are waiting for delivery of Tentor Bars we offer our apologies and our gratitude for their patience and forbearance. We are doing everything possible at this end to speed things up and to meet requirements as soon as possible.

Tentor Bars are supplied by the following companies and their branch offices:—

B.R.C. STEEL LTD.,
Silkmore Lane, Stafford. Stafford 444

G.K.N. REINFORCEMENTS LTD.,
197 Knightsbridge, London, S.W.7.
KENington 6311

McCALL & CO. (SHEFFIELD) LTD.,
P.O. Box 41, Sheffield. Rotherham 2076

STEEL, FEECH & TOZER, LTD.,
Branch of The United Steel Companies Ltd.,
The Ickles, Sheffield. Sheffield 41011



Technical enquiries to:

THE TENTOR BAR COMPANY LTD.,
197 Knightsbridge, London, S.W.7
Telephone: KENington 6311
Telegrams: TENTORED, London, S.W.7

The
TENTOR BAR
Company Limited



TENTOR BARS Registered Trade Mark

GLASGOW

NEWCASTLE

LEEDS

MANCHESTER

LEICESTER

BIRMINGHAM

LONDON

BRISTOL

CARDIFF

STAFFORD

DUBLIN

LIVERPOOL

BELFAST

BRC

Specialists in Reinforced Concrete Design and Suppliers of Reinforcement, with Design and Branch Offices strategically placed throughout the British Isles

The BRC service includes a Site Investigation Department

**REINFORCED CONCRETE IS
CONSTRUCTION AT ITS BEST**

There are vacancies for experienced engineers in several of our design offices.

The British Reinforced Concrete Engineering Co. Ltd., Head Office & Works: Stafford